

SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1901, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.


Vol. LXXXIV.—No. 18.
ESTABLISHED 1845.

NEW YORK, MAY 4, 1901.


\$3.00 A YEAR.
8 CENTS A COPY.




Nile Reservoir Works, Assiut—Upstream Side of Piers, Looking West.




Assouan Dam—Water Rushing Through Central Sluices.



Work at the West Bank, Assiut.



Centrifugal Pumps at the Foundation Excavations.



Composite Metal and Masonry Construction, Assouan.

CONSTRUCTION OF THE GREAT NILE RESERVOIR.—[See page 279.]

Scientific American.

ESTABLISHED 1845

MUNN & CO., - - - EDITORS AND PROPRIETORS.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, - - NEW YORK.

TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico \$3.00
 One copy, one year, to any foreign country, postage prepaid. £0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845) \$3.00 a year
 Scientific American Supplement (Established 1876) 5.00 ..
 Scientific American Building Edition (Established 1885) 2.50 ..
 Scientific American Export Edition (Established 1878) 5.00 ..

The combined subscription rates and rates to foreign countries will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.

MUNN & CO., 361 Broadway, corner Franklin Street, New York.

NEW YORK, SATURDAY, MAY 4, 1901.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

THE NORTH RIVER BRIDGE BILL.

The storm of opposition, which has been aroused in New York by the passage of the North River bridge bill by the New York Legislature, is directed not against the bridge itself, nor even against the proposed elevated structure from Fifty-ninth Street to the Battery; for the erection of the bridge has come to be regarded as a necessity, and the extension of the bridge tracks along the Hudson River waterfront is admitted to be the necessary concomitant of the bridge itself. The present violent opposition is based upon the fact that, in giving to a private corporation the right to build an elevated structure along five miles of the city's waterfront, on the payment of a merely nominal consideration, the Legislature is practically handing over to private individuals property which, in the estimate of ex-Mayor Hewitt and the present Comptroller of the city, may easily prove to be worth from sixty to a hundred million dollars.

The North River Bridge should be built, and if private capital wishes to undertake such a gigantic scheme, it should be encouraged by all proper legislative assistance. To render the bridge effective, its tracks should certainly extend south from Fifty-ninth Street throughout the full length of the city's waterfront. But that any private corporation should be allowed to secure such a practical monopoly of ocean and river traffic as would result from the carrying out of the present bill, is not to be thought of for a moment. The present city government, the leading commercial bodies of the city, and the most prominent of its present and past officials, are unanimous in condemnation of the extraordinary audacity displayed in the present bill. If a franchise for the construction of the West Street line is to be granted, it should only be done subject to such conditions as are suggested by ex-Mayor Hewitt, namely, a rental equal to the interest, with a contribution to the sinking fund for the repurchase of the property within fifty years, and with the power of resumption by the city at any time during that period by paying the amount actually spent on the work plus a reasonable percentage. We are inclined to think, however, that in view of its enormous and ever-appreciating value, a railway of this kind giving access to all the docks, would develop such a vast earning capacity that the city could not do better than undertake the construction and ownership itself. The company that owned the combined bridge and approach would absolutely control the shipping situation in New York, and there would always be the temptation to operate the system on the vicious principle of charging up to the limit of what the traffic would bear, thereby sacrificing the interests of the city as a shipping point to those of the shareholders of the company.

From an engineering point of view the scheme is entirely feasible. Looked at from the standpoint of operation, moreover, there is everything to be said in its favor. The proposed bridge will have a capacity of six or eight main-line railroad tracks, and it will doubtless be capable of accommodating all the traffic from the West which now finds a terminus in Jersey City. Freight could be carried from any western shipping point, direct across the Hudson River, down the West Street elevated structure, and switched off, if need be, on to the steamer pier at which it was to be unloaded—an ideal traffic arrangement, and one to which New York city is bound ultimately to come, if it is to maintain its position as the chief shipping point on the Atlantic coast.

It is sincerely to be hoped that after Governor Odell has heard the committees from New York which are opposed to the bill and has looked at all the bearings of this momentous question, he will veto the measure and leave it for the bridge company and the city authorities to make an equitable arrangement which will be mutually profitable.

RE-ROLLING OLD STEEL RAILS.

During the past five years, there has been developed a method of utilizing old steel rails which bids fair to become an important factor in the steel industry. When steel rails were first introduced, the question arose as to what disposition could be made of them when they had been so far worn out as to be unfit for further service, and it was not until the introduction of open-hearth furnaces that it became possible to cut up the old rails and remelt them with pig iron and scrap from the stockyard.

About ten years ago Mr. W. E. McKenna, one of the officials of the Chicago, Milwaukee and St. Paul Railroad, turned his attention to the problem of utilizing these worn-down and defaced rails by re-rolling them to a size somewhat smaller than the original section. After considerable experimental work, the first of which was done in 1895, it was determined in 1897 to erect a plant for the special purpose of re-rolling old rails. The first plant was erected at Joliet, Ill., and in 1898 a second plant was built at Kansas City, Mo. At the present time over a thousand miles of track have been relaid with rails that have been passed through the re-rolling mills, a total of nearly one hundred thousand tons having been thus treated, by the new system.

The wear upon the rails is, of course, chiefly on the top and inside of the head of the rail. In the process of re-rolling, the rails are very slightly reduced in the webs and flanges, while the contour of the head is restored to a symmetrical, though somewhat smaller section. Briefly stated, the process consists in first passing the rail beneath a set of grinders, which take off the slivers and rough edges from the head, then heating them in a special furnace to a temperature of 1,700 degrees, and rolling them down to the desired section, the rails passing out of the finishing rolls at a temperature of 1,480 degrees. The rails are then sawed to proper length, straightened, and the holes drilled for the angle bars.

The thorough working over of the metal at such a comparatively low temperature serves to improve its quality, not chemically, of course, but by virtue of the density and toughness which result from a thorough working over of steel and iron. The reduction of the section of the rail produces a corresponding elongation, a 30-foot rail being increased by 1 to 2 feet in length for a reduction of cross section of 8 per cent. The value of this system is obvious, particularly in view of the fact that theoretically the oftener a rail is re-rolled the better its quality. Since many of the great railroad systems use as many as three or four different weights of rail, according to the character of the traffic in different localities, it is evident that re-rolling will result in considerable economy, worn rails of a section being simply sent to the mills and rolled down to a section suitable to other divisions of the road.

NITRO-CELLULOSE VS. NITRO-GLYCERINE SMOKELESS POWDERS.

The facts brought out in an article by Lieut. A. T. Dawson, late of the Royal Navy, in a paper read before the English Society of Arts regarding the behavior of the British smokeless powder, cordite, are a decided indorsement of the wisdom of the Naval Ordnance Bureau in directing its attention to the development of pure nitro-cellulose, or all-gun-cotton, smokeless powder. Nitro-glycerine, on account of its great explosive energy, is an attractive ingredient in the manufacture of smokeless powder; but it has the great defect that the temperature of explosion is abnormally high and that the erosion of the interior surface of the gun is proportionately increased. The South African campaign has afforded an excellent opportunity to judge of the amount of this deterioration, and it is a fact that many field pieces in the Transvaal have been returned badly eroded, and that several of the 4.7-inch guns supplied from the navy were in constant need of replacing, the wear and tear of service having completely spoiled the shooting qualities. Variations of 400 yards in the range have been experienced with guns that had been some time in service and were badly eroded.

These results may be compared with those mentioned in the last report of Rear-Admiral O'Neil, in which it is stated that tests carried out by the Bureau of Ordnance with the navy nitro-cellulose powder prove that there is practically no erosion whatever, a 4-inch rapid-fire gun at the Indian Head Proving Ground having been fired 661 times, and a 5-inch gun 636 times, without causing any wear that could be detected by micrometer measurement.

Some of the nitro-cellulose powders used on the Continent have given ballistic results which entirely disprove the off-repeated assertion that, weight for weight, cordite possesses much greater power than any nitro-cellulose compound. In a recent trial of a 45-caliber 6-inch gun, a charge of 28.6 pounds of cordite gave a velocity of 2,873 foot-seconds, while 36 pounds of Rottweil nitro-cellulose powder gave 2,910 foot-seconds. The corresponding energy for 2,910 foot-sec-

onds is 5,872 foot-tons, whereas the velocity developed by the same gun in service, using cordite, is only 2,530 foot-seconds, equivalent to 4,438 foot-tons, or 32 per cent less energy. A further advantage of high velocity is the increased danger space, which in a 6-inch gun with 3,000 foot-seconds is 465 yards as against 226 yards in the case of the service 6-inch guns using cordite.

THE SMITHSONIAN REPORT.

Dr. S. P. Langley's report of the Smithsonian Institution for the year ending December 30, 1900, deals with the Institution proper, the United States National Museum, the Bureau of American Ethnology, the International Exchanges, the National Zoological Park and the Astrophysical Observatory. The total permanent fund now amounts to \$912,000, and is deposited in the Treasury of the United States and bears interest at six per cent per annum, the interest alone being used in carrying out the aims of the Institution.

Congress charged the Institution during the fiscal year 1900 with the disbursement of \$397,540, of which the National Museum received the greater part, although the grants of \$75,000 to the National Zoological Park and \$50,000 to the Bureau of American Ethnology may be regarded as a very satisfactory disposal of public funds. Appropriations made by Congress for the fiscal year 1901 were \$428,540. The Institution has continued research work in various fields of science, including experiments in the solution of the problem of mechanical flight, and, through its Astrophysical Observatory, investigation on the solar spectrum. The Institution has made some interesting experiments during the year on "radio-active substances." The different branches of research now progressing under grants from the Hodgkins fund are making satisfactory advances. The income of the Hodgkins fund is devoted to investigations of the properties of atmospheric air. In accordance with the urgent desire of many of the leading biologists of the country a contract for a table in the Naples Zoological Station for a third term was entered into, and the appointments to the seats were at once approved. While it has never been possible for the Institution to devote a large amount of its income to carrying on explorations, it has, nevertheless, been able to promote such work in various ways, particularly in connection with the bureaus of the Institution and in co-operation with the executive departments of the government. These explorations have a very wide range, and are productive of a very great increase in the knowledge of natural history of the region visited, and of the ethnological conditions of the people. During the past year the Institution has thus been more or less directly concerned in explorations in various parts of the world, from the Arctic regions as far south as Patagonia, and in the distant possessions in the Philippines, as well as in South Africa.

Through the publications of the Institution and its bureaus much is done each year in carrying out its fundamental object, which is the "diffusing of knowledge." Works covering practically every branch of the human industries have been distributed throughout the world to librarians and institutions where they may best be available to scholars and to the reading public. The number of volumes, parts of volumes, pamphlets and charts given to the library has aggregated 25,701, and now only completed volumes are entered in the accession book. The secretary notes with regret the failure of Congress to make an appropriation to send a representative to the conference on the International Catalogue of Scientific Literature held in London.

Dr. Langley states that he is fitting up in the southern tower of the Smithsonian building a small room which is to be called the "Children's Room." The little group of specimens which it contains is meant to stimulate interest and imagination rather than to ostensibly instruct. Latin is banished from its labels, and the classification is not that of science but that which is most intelligible to the untrained minds. This room will, without doubt, prove very attractive to children and will probably be taken as a model the same as is the Children's Museum of the Brooklyn Institute, which we have illustrated.

The correspondence of the Institution embraces letters having reference not only to the scope and work of the Institution, but also relating to the bureaus placed by Congress under its direction. A part of \$300,000 appropriated for a government exhibit at the Pan-American Exposition has been apportioned to the Smithsonian Institution and its bureaus. The collection will chiefly consist of specimens illustrative of its scientific functions and more especially of the National Museum and Bureau of Ethnology.

Robert Ridgway, Curator of Ornithology in the National Museum, published, a number of years ago for the use of the naturalist, a handbook on color, and he requested a grant from the Institution for a new edition. It appeared to the secretary that a work upon a more extended scale and a somewhat different plan would be of value, primarily to the naturalist,

but also in every department of science, to artists and in many branches of industry. A committee has been appointed to consider the subject, as the work promises to be of considerable magnitude, and the results will be looked for with interest.

The Secretary calls attention to the necessity for an increase in the National Museum buildings, which are entirely inadequate. The field of the work of the corps of the Bureau of American Ethnology extended into Maine, New York, Minnesota, Wisconsin, Indian Territory, Oklahoma, California, Arizona, New Mexico, Cuba, Ontario and Nova Scotia, while especial work was done in other districts. The explorations and researches continue to yield valuable results in the form of contributions to the science of ethnology, while the collections made in connection with the work form an important tributary to the National Museum. Some practical importance attaches to the recent work of the bureau in connection with aboriginal agriculture and crop plants. The investigation of the wild-rice industry of the north lake region especially brings out a neglected phase of aboriginal industry and at the same time directs attention to a promising natural resource.

The free interchange of government and scientific publications between this country and the learned of other lands has grown to be one of the most important functions of the Smithsonian Institution. Great numbers of books are annually transported abroad and great quantities are received in exchange each year, the quantity handled aggregating 113,563 packages, weighing 409,991 pounds. The exchanges are in no sense of a commercial nature, for no publications for sale are allowed transmission. It is interesting to note that the expenses of the exchange service were for thirty years made entirely from the income of the Smithsonian Institution, but when public documents began to form so large a part of the transmissions as to become an unbearable strain on its resources, Congress began to make appropriations for the work.

The National Zoological Park is being constantly made more interesting by the introduction of new specimens. The extremely limited appropriations allowed by Congress have made it almost impossible to carry out the original programme of procuring a large collection of specimens of our native animals. The Astrophysical Observatory possesses a considerable quantity of apparatus which was employed in the observations on the solar eclipse of May 28, 1900, and we shall take pleasure in publishing in a subsequent number of our SUPPLEMENT full particulars of the work of observing the eclipse.

On the whole the Smithsonian Institution seems to be admirably administered with a view to carrying out the wishes of the original founder.

THE BALDWIN-ZIEGLER EXPEDITION TO FRANZ JOSEF LAND.

During the coming summer an expedition is to be sent to Franz Josef Land. It will be known as the Baldwin-Ziegler Expedition, and will be under the direct command of Mr. Evelyn B. Baldwin, formerly of the United States Weather Bureau. It is understood that the cost of the undertaking will be borne by Mr. William Ziegler, a wealthy and public-spirited resident of New York city. The principal objects of the expedition are to make magnetic, meteorological, gravity, and astronomical observations, in addition to surveying and hydrographic work, for which elaborate preparations are being made. It is also intended to make extensive collections of the flora and fauna of the region, as well as to gather specimens which will adequately represent the geographical formations.

The expedition will take two steam whalers and one or more steam launches, the latter being designed especially for use in shallow waters.

Franz Josef Land, once believed to be a continent and now known to consist of a group of islands, lies in the Arctic Ocean, north of Novaia Zemlia. It is in a higher latitude than any other known land in the eastern portion of the Polar Basin. It was discovered by an Austro-Hungarian expedition in 1873. The region was penetrated by a sledging party for a distance of about 125 miles. Payer, the commander of the land party, advanced up Austria Sound as far as Cape Fligely (82° 5' north lat.) from which point—1,000 feet above the level of the sea—he observed mountains far away to the north, beyond the 83d degree. At this point it may be stated that Jackson, who visited the region later, found that no such land as Petermann Land existed. To the northwest high land rose above the open water. In the vicinity of the cape bears and foxes were plentiful, and seals were observed in large numbers about the edge of the ice. The abundance of animal life was most propitious for the explorers. Several eminent authorities regard this region as a most favorable starting-point for future journeys northward. Admiral Sir George Nares, of the British navy, went so far as to say that its extreme importance as a base for future operations has been proved. Admiral Albert Markham, in his recent work on Sir John Franklin, regards the region as "the

objective from which future Arctic exploration should be carried out." Admiral Sir Erasmus Ommaney declared that "as all other points afford no hopes of penetration to the northward, we must now accept Franz Josef Land as the base for future operations;" and Sir Allen Young in like terms considers that it must be regarded as "the only land extending far to the north by which such journeys can be made."

The now celebrated Jackson-Harmsworth Expedition visited this land in 1894 and remained there for three years. While their object does not seem to have been to actually reach the North Pole, the hope was indulged that a thoroughly scientific exploration of Franz Josef Land might be made and that they might reach a point so far north as to afford facilities for a nearer approach to the North Pole than had hitherto been accomplished.

With the aid of his co-travelers Mr. Jackson found Franz Josef Land to consist of numerous islands instead of a continent, as had been previously believed. The idea of gaining a very high latitude was therefore abandoned, their special efforts being then devoted to a thorough examination of the group. Magnetic, meteorological and other observations were taken constantly and collections made in almost every branch of natural history. Winter quarters were established on Northbrook Island to the southwest of the group. Walruses, bears and seals were found in abundance. During the three years of their stay at the island the "Windward" paid a visit, but being frozen in, was compelled to remain a year. It returned with supplies in July, 1896. A month previous Dr. Nansen and Lieut. F. H. Johansen, who wintered in Franz Josef Land about 100 miles from Jackson, arrived at the island in their kyaks, and a cordial welcome was given them. In the following summer the "Windward" again



MR. EDWARD B. MOORE,
Assistant Commissioner of Patents.

visited Franz Josef Land, and on this occasion Jackson and his party returned home.

The collections which they made included rocks, fossils, silicified wood, plants, including phænogams, cryptogams, and lichens; eggs of snow bunting, eider duck, glaucous gull, kittiwake gull, ivory gull, Richardson's skua, Brünnich's guillemot, black guillemot and little auk; and birds, including the snow bunting, Lapland bunting, shore lark, common swallow, snowy owl, jerfalcon, Brent goose, eider duck, turnstone, Bonaparte's sandpiper, sanderling, Arctic tern, Ross' gull, glaucous gull, ivory gull, kittiwake, Richardson's skua, pomatorhine skua, Mandt's guillemot, little auk, Brünnich's guillemot, red-throated diver, and fulmar petrel. No traces of previous human occupation were found by the explorers.

Shortly before sailing from England in 1894 Mr. Jackson read a very interesting paper before the Royal Geographical Society of London, in which he summed up the advantages of the region for exploring purposes under these four principal heads:

"I. The accessibility of Franz Josef Land late in the summer when approached along the meridian of 45° E., or some meridian between that of 45° and 50° E. This accessibility has been proved, in my opinion, by the voyages of Mr. Leigh Smith and the little Dutch ship 'Wilhem Barents.'

"II. The northward extension of Franz Josef Land to a latitude as high as 82.5° at Cape Fligely, and some twenty or so miles further if we accept Payer's view that Cape Sherard Osborne is continuous with that portion of the country he called Prince Rodolf's Land. The long stretch of *terra firma* forms a safe route for advance or retreat, and provides all we need in the way of sites for our depots and cairns.

"III. The still further extension to the north of what, perhaps, I should call the Franz Josef Land group. Standing on Cape Fligely, Payer saw, sixty or seventy miles to the north, the high outlines of an ice-covered

land of apparently large extent. This he called Petermann Land, and this land lies undoubtedly in a latitude as far north as any yet reached. There is absolutely nothing known of it beyond this, but it is a reasonable hypothesis to maintain that a land of such elevation would probably reach at least to the eighty-fourth degree north latitude, and who knows how much further?

"It is this land we shall try to reach after we have safely landed, and in the early days of the following spring marched over the ice of Austria Sound, a gulf which penetrates the country to Cape Fligely; or if this be not so favorable to us as it proved to Payer, along the shores that reach down to the Sound.

"IV. The fourth consideration is provided by the observations of Payer, confirmed by the winter experience of Mr. Leigh Smith. And this consideration is a strong one—the great abundance of animal life on the southern shores of Franz Josef Land during the winter as well as in the summer."

Although the results of exploring expeditions have always been hazardous subjects of speculation, it is confidently expected that the enterprise of the present year will be at least as successful as any that have yet been made in that region, while it is natural to hope that our American effort will eclipse all others in brilliancy of exploit and results of practical usefulness, and perhaps even pave a definite pathway to that long sought goal of explorers—the North Pole.

THE NEW ASSISTANT COMMISSIONER OF PATENTS.

The new Assistant Commissioner of Patents, vice Walter H. Chamberlain, resigned, is Mr. Edward B. Moore, late Principal Examiner of the Thirty-fifth Division of the Patent Office. Mr. Moore was born at Grand Rapids, Mich., and he entered the Patent Office some fifteen years ago and at once set himself resolutely to the task of fitting himself for promotion. Eleven years later he was appointed to the position of Principal Examiner and later made a Chief Examiner of the office. Mr. Moore was chosen to represent the Patent Office at the recent Paris Exposition. The Office made no formal exhibit on that occasion, but many interesting models were loaned for exhibition purposes. Mr. Moore has had under his supervision the examination of all cases relating to educational appliances, accouterments, baggage, advertising devices, bundle carriers, fluid pressure regulators, packing and storing vessels, buckles, buttons and clasps, constituting a very wide range of subjects and involving extended technical knowledge upon his part.

Mr. Moore is noted for the justice of his decisions, by which the interests of the inventor and those of the public are equally safeguarded. In his new office Mr. Moore will have an excellent opportunity of again demonstrating his fitness as to the general and technical requirements which are imperatively demanded for the effective performance of the difficult and responsible duties which devolve upon the Assistant Commissioner of Patents.

OPENING OF THE PAN-AMERICAN EXPOSITION.


The gates of the Pan-American Exposition were closed on April 21, and every available man was put to work in order to offset the damaging effects of the severe snowstorm which visited Buffalo. The damage to the buildings is very slight, but the delay in the landscape work and the building of roadways is a great hindrance. It was intended to have this portion of the work so complete that it would be possible to have the Fair practically complete on the opening day. The storm, however, was so severe that the managers decided to postpone the formal opening until Dedication Day on May 20. It is not intended to postpone the actual opening, but there will be no ceremonies until May 20. As the Fair will be very complete at that time and the weather will probably be better, the change seems to be a wise one. The first two weeks of every fair that has ever been held have seen incompleting buildings and empty exhibition spaces.

According to German press reports, the project involving the construction of an electric railway between Rome and Naples, which was agitated some time ago but afterward abandoned, has been revived. Two Neapolitan engineers, it is stated, have prepared new plans for the road, which have been submitted to the ministry of public works. The contemplated railway will run along the shore via Cancelli, Mondragone, Minturno, Formia, Fondi, Terracina, and Cisterna to Rome, with a branch line, by way of Marano and Guigliano, to Capodimonti, the summer residence of the King. It will be double-tracked, with a total length of 135 miles.

A Swiss engineer named Sutter nearly lost his life while conducting some experiments with his airship at Arbon, near Lake Constance. His airship is similar to that of Count Zeppelin. The machine rose to a height of 150 feet, and then became unmanageable and fell.

A PERPETUAL MOTION CLOCK.

At the Paris Exposition there was exhibited a clock which ran for two months without having to be wound up, therefore the makers were somewhat justified in calling it a "perpetual motion clock." The inventor obtained his result by combining a system of jointed levers or armatures with permanent magnets in order to permit the wheel to revolve indefinitely around its axis to coil a spring. The principle is based upon the fact that poles of the same name repel, while those of opposite names attract. Two series of movable levers are placed upon the faces of the rim of a large wheel. The two arms of such levers form between them an angle of forty-five degrees; the shorter one is provided at its extremity with a weight which acts as a counterpoise. The counterpoise most distant from the center has a preponderating action upon the side of the wheel. It makes four revolutions a minute, and actuates a regulating flywheel through the medium of an endless chain. The frame of the apparatus is constructed of magnetized steel. It supports the axle of the wheel and is surmounted by a roller that constitutes a pole. When in its motion the wheel brings the short arm of one of the levers opposite the roller, the phenomenon of repulsion is produced. We are indebted to La Vie Scientifique for our engraving.



A PERPETUAL MOTION CLOCK.

LAUNCH OF THE WHITE STAR LINER "CELTIC."

The launch at Belfast of the huge liner "Celtic" marks another great step of the rapid growth in size of the modern steamship. This truly gigantic vessel is easily the largest steamship ever constructed, for on her maximum draught of 36 feet 6 inches she will displace 37,700 tons, which is more than double that of the heaviest battleship afloat, and 10,300 tons more than that of the "Great Eastern." The next largest steamship is the "Oceanic." When they are completed, the big freighters under construction at New London, Conn., which, it is claimed, will be of 33,000 tons maximum displacement, will equal the "Oceanic" in size.

The "Celtic" is 700 feet long, her beam is 75 feet, and her depth 49 feet. She measures 20,880 tons gross, and 13,650 tons net. How these dimensions compare with those of other well-known liners is shown in the tabulated statement below. Gross tonnage is used in the table, and the lengths given are over all.

As will be observed, she is a few feet shorter than the "Oceanic," with, however, 7 feet more beam. She is, as the figures also show, the first vessel to exceed 20,000 tons. The task of building such a vessel was necessarily very heavy, and possibly there are not half a dozen ship-building yards in Great Britain which could have looked at it.

The shell plates of the "Celtic," of which there were 1,392, averaged 30 feet by 5 feet, were an inch and a quarter thick, and in some cases weighed as much as 4 tons. Machine riveting was adopted wherever possible in the keel, double bottom, hull, and stringers; 167,095 inch and quarter rivets were driven in this way.

There are altogether nine decks, and as their arrangement in some way facilitates the task of describing the vessel, the names may be given. They are—lower orlop, orlop, lower, middle, upper, bridge, upper bridge, boat, and sun decks. With obvious exceptions they are all real plated decks and of full length. The greatest

care has been taken to secure her against the alternate hogging and sagging stresses she will experience. She has a flat bar keel riveted onto the skin plating

sheer strake and the next but one lower are also doubled and the upper deck stringers have been treated similarly except at the extreme ends. Strength fore and aft is further secured by six longitudinals worked intercostally, three on each side of the inner keel; with the thwartship vertical divisions these make the cellular double bottom, which is bounded by margin plates and covered by the inner skip plat-

Vessel.	Length. Ft. In.	Breadth. Ft. In.	Depth. Ft. In.	Tons.
Great Eastern.....	691 0	82 8	48 2	18,915
Britannic.....	468 0	45 2	33 7	5,004
City of Rome.....	500 0	52 3	37 0	8,144
Alaska.....	520 0	50 0	38 0	6,400
Etruria.....	520 0	57 3	38 2	7,718
Paris.....	560 0	63 2	39 2	10,500
Teutonic.....	582 0	57 8	39 2	9,984
Fürst Bismarck.....	520 0	57 6	38 0	8,744
La Touraine.....	540 0	56 0	34 6	9,209
Campania.....	620 0	65 0	43 0	12,950
Kaiser Wilhelm der Grosse.....	648 0	66 0	43 0	14,349
Oceanic.....	705 6	68 0	49 0	17,274
Deutschland.....	686 0	67 0	40 4	15,540
Celtic.....	700 0	75 0	49 0	20,880


ing. At the sides the frame brackets are attached to the margin plates by double angles, and the floor plates have been similarly treated. And to further increase the longitudinal stiffness there are two intercostal keelsons running fore and aft. At the decks, too, there is a beam to every frame, so that care could, to no greater extent, ensure a stoutly built ship. The arrangement for carrying the propellers is exactly that of the "Oceanic," and the rudder is of cast steel sections bolted together. The engines are of Harland & Wolff's quadruple expansion "balanced"

type, with cylinders of 33, 47½, 68½, and 98 inches diameter. The stroke is 5 feet 3 inches. Steam will be supplied at a pressure of 210 pounds by eight double-ended boilers, each 15 feet 9 inches by 19 feet 6 inches. The vessel is not intended to be a record-breaker.


There are quarters for, altogether, 2,859 passengers and a crew of 335. The first class accommodation is on the upper, the bridge, the upper bridge, and the boat decks, and corresponds to that of the "Cymric." The number of first-class passengers provided for is 347. Aft on the upper and bridge decks there are quarters for 160 second-class passengers. Third-class passengers to the number of 2,352 are provided for on the upper, middle, and lower decks, some in staterooms and others in open berths.

The launching arrangements were those which worked so successfully in the floating of the "Oceanic," with the necessary difference for the greater weight that the chain was an eighth-of-an-inch thicker. The displacement of the hull was, it may be noted, no less than 13,500 tons. A massive steel casting, containing a hydraulic cylinder and ram, and a trigger half let in to a steel-shod niche in the sliding ways, was fixed in the standing ways. The lower half of the trigger was held in position by the ram until all was clear, and with the release of the pressure the upper half dropped flush with the ways. As the hull was water-borne its progress was checked by the dropping, pair after pair, of three pairs of anchors.

The official laboratory at Hamburg has discovered that the sand which fell during the recent snow-storm in southwestern Germany came from the African Sahara.



THE "CELTIC" ON THE STOCKS.




Length, 700 feet; beam, 75 feet; depth, 49 feet; maximum displacement, 37,700 tons; Speed, 16½ knots.

THE LAUNCH OF THE "CELTIC," THE LARGEST SHIP EVER CONSTRUCTED.

French Wine Production of 1900.

The wine production of France for the year 1900 is 1,721,000,000 gallons, a yield that has only been exceeded three times in the past century. The promise of a large yield was so great in August that sales were made at less than a dollar per barrel for a good table wine. Of course, the high-grade wines brought large prices. Since early in the seventies up to 1900 there has been a great demand for American plants for grafting upon French vines. In 1881 the total area replanted with American vines was 21,262 acres; in 1889 it was 471,000 acres, and to-day it is 2,414,495 acres. The old vineyards which were destroyed by the phylloxera have been "reconstituted," as the French say, by graftings from the United States, and it is believed that they are now phylloxera-proof. The acreage planted in vines in France has been steadily increasing during the last twenty years, but there are reasons for believing that it has come to a standstill. The organs of the wine growers advise that



Typewriter, with mechanical attachment, at the receiving station, on which, by the turning of a crank, the message is translated from the perforated characters on the tape to the printed characters on the page.

MR. MURRAY OPERATING A RECEIVING STATION PRINTER.

attention be paid now to quality and not quantity. It is probable that the octroi tax will be abolished within a few months, and wine will enter the gates of all the cities of France duty free. It is hoped that this will have the effect of increasing the sale of wine and decreasing the consumption of alcoholic liquor. If the production of wine remains stationary more land will be devoted to the raising of early fruits and vegetables. The planting of mulberry trees and the raising of the silkworm will receive more attention. Wine is now produced more cheaply in California than in France, and the efforts to introduce French wines into Japan have not been effectual on account of Californian competition, the Japanese declaring they can buy wine cheaper in San Francisco than in France. The grape growers of France expect an absolute immunity from losses by hail by the use of cannon, and a newspaper which is the organ of the hail destroyers has just made its appearance.

Experiments have been carried on at Cape Town in which motors are used for transporting Maxim guns. The gun was mounted on a platform and occupied the front seat of a quadricycle.

THE MURRAY PAGE-PRINTING TELEGRAPH.


The valuable invention which forms the subject of the present article is the work of a young Australian journalist; and it takes on particular interest from the fact that its author at the time he entered upon the investigation which has resulted so successfully was absolutely without knowledge of telegraphy. The earlier experiments were carried on in Sydney, and as soon as Mr. Murray had satisfied himself that his system was mechanically and operatively practical, he left at once for the United States for the purpose of securing his patents and introducing his system. His success has been thorough and rapid, for while his many applications for foreign patents were still pending, he made arrangements with the Postal Telegraph Company for the exclusive telegraphic rights to his invention in the United States.

Among the problems connected with telegraphy which have commanded the earnest efforts of inventors is that of automatically printing messages in the Roman characters. From time to time we have illustrated, either in the SCIENTIFIC AMERICAN or the SUPPLEMENT, the most successful inventions in this difficult but fascinating field of investigation. The demands of telegraphy are so various that it is not to be expected that any single printing telegraph can be produced that will answer for every class of telegraphic work,

and all the machines of the kind that are in use, or proposed, belong to one or other of three or four types.

The simplest form of printing telegraph is the well-known "stock-ticker," the perfected form of which is found in the Burry page-printing telegraph, which was illustrated in the SCIENTIFIC AMERICAN of March 23, 1901. These machines, although they might be used in long-distance telegraphy, are designed more particularly for city use in the disseminating of news from a central station to a large number of separate private offices. Another class of printing telegraphs

is that which is devoted mainly to long-distance telegraphy, as represented by the vast business of the leading telegraph companies, where speed and accuracy become of prime importance. It is only within the last year or two that efficient machines of this class have been perfected. One of these, invented by Donald Murray, is in use by the Postal Telegraph Company,



The typewriter, G, is removed to show the interlocking mechanism, H, by which the perforated characters on the tape are made to strike the keys of the Roman alphabet on the typewriter.

RECEIVING STATION PRINTER.

and another, invented by Charles L. Buckingham, is being operated by the Western Union Company. In the same class are Rowland's and Baudot's multiplex-printing systems. Another class of telegraphy, to which belong the Delaney, the Squier and Crehore, and the Pollak-Virag, has not as yet established itself commercially; for with its speed of over a thousand words a minute, it is perhaps ahead of its time, since there is not sufficient telegraphic business of the kind required to keep such systems going at this enormous rate of speed.

It is impossible within the space at our disposal in the SCIENTIFIC AMERICAN to give a detailed description of Murray's most ingenious and successful telegraph. For this the reader is referred to a paper recently presented before the American Institute of Electrical Engineers, which is given in full in the SCIENTIFIC AMERICAN SUPPLEMENT of February 2 and February 9 of this year. The accompanying diagrams and photographs, however, show a complete installation, from the keyboard perforator at the sending station to the printer at the receiving station, and the subjoined description is sufficiently ample



At the transmitting station the blank tape is punched with perforated characters in typewriter punching machine, A; then run through a modified Wheatstone transmitter, B. At the receiving station the impulses are controlled by relays, C, and a vibrator, D, and operate a punching magnet, F, which reproduces the perforated characters upon a blank tape. This tape is then run through an attachment, H, to a typewriter, G, which latter prints the message in page form in the Roman characters.

COMPLETE SET OF MURRAY PAGE-PRINTING TELEGRAPH APPARATUS—HIGHEST SPEED 130 WORDS PER MINUTE.

to give a comprehensive idea of the principles and operation of the system.

The fundamental feature in the Murray system is the use of a perforated tape, which is divided lineally into exactly equal spaces of half an inch, each space representing a character. Each character-space is theoretically divided into five subdivisions, and the characters are determined by the number and sequence of the perforations in each letter-space. The perforated tape is run through a modified Wheatstone transmitter at the transmitting station, and the impulses, thus set up, serve to operate a magnetic perforator at the receiving station, which produces a facsimile of the transmitting tape by means of a punching magnet whose strokes correspond in frequency with the impulses received. The perforated tape produced at the receiving station is then run through a printer, whose operation is substantially the same as that of a pianola or automatic piano.

The punching machine, A, which in appearance is not unlike a typewriter, is so constructed that, as the tape is run through the machine, the striking of each key makes the proper combination of perforations in each half inch of character space. The prepared tape is ruled off into half-inch spaces and has a central line of fine perforations, which serves to engage the feed-wheels in the puncher and transmitter. There are ten small punchers, which are so arranged that five of them register on each side of the central line of perforations just referred to, and it can be easily understood that by the use of a system of interlocking bars the desired combination of punchers can be driven down at the stroke of each key. In all, 84 different characters may be punched.

As soon as a message has been punched by the operator, it is torn off by a boy who inserts it in a modified Wheatstone transmitter, B, which performs the functions of an ordinary telegraphic key. The tape is fed by means of an electrical pendulum-motor, driving a small star-wheel, which engages the central line of perforations and draws the tape through the machine. As the tape advances, the prickers, 4 and 5, which are located in line with the advancing lines of perforations in the tape, pass up through the perforations, and by their vertical oscillation give movement to reciprocating rods, 6 and 7, which serve to engage respectively with opposite terminals of a switch-arm, 8. The impulses thus set up are transmitted, let us say, from Chicago to New York, where they repeat, in sequence and frequency, the combinations of perforations in the tape. At the receiving station there is a main line relay, which governs a punching magnet in the perforator, F; also a governing relay, which maintains unison between the main-line impulses as they arrive and the corresponding impulses in the local circuit. This group of relays is indicated in our photograph by letter C. The local impulses are created by a vibrating reed (D, in photograph—11, diagram). The impulses as received at New York are utilized to perforate a blank tape which is a facsimile of the tape used in transmitting from Chicago.

The perforator, F, consists of a punching magnet and a spacing magnet. The tape is fed into the machine by a star-wheel (35, diagram) which is driven by a small motor; upon the same shaft as the star-wheel is an escapement controlled by the spacing magnet. The vibrating reed, 11, makes and breaks the local circuit of the spacing magnet. The impulses are so utilized, electrically, that the tape, as it leaves the machine exhibits perforations corresponding to those sent out from the Wheatstone transmitter at Chicago. The next operation is the important one of automatically transferring the perforated characters on the tape to a printing machine, which produces them in page form in the Roman characters. This is done by means of a typewriter, G, whose key levers are operated by an exceedingly ingenious combination of five transverse locking combs and a set of vertically-oscillating levers (41, in diagram; also H, in photograph). The combs terminate in five pointed rods, 40, the ends of the rods registering with five perforations in a plate, 38. The tape is caused to travel between the perforations in the plate and the pointed

ends of the combs, the tape being drawn along a half-inch, or the length of one character, at each step. At the instant when the perforations of the tape coincide with the pointed ends of the bars, the plate is brought forward. Only those combs are moved longitudinally whose pointed ends correspond with the unperforated subdivisions of the tape, the other points projecting through the perforations in the tape and the die, and remaining stationary. Without pursuing the description any further, it can be seen at once, by reference to the diagrams, that the combinations thus formed of notches, 39, on the upper edge of the combs with the vertically oscillating strips, 41, above them, will result in the proper key lever from the typewriter above dropping into the clear groove thus formed. The moment it does this, a motor-driven cam engages it, produces a movement of the typewriter lever, and so prints the Roman character desired.

Such, in brief, is the system employed by Mr. Murray, and in the long-distance tests which have been made between Chicago and New York and Boston and New York a speed of 102 words per minute has been realized; and on a line 384 miles long, a speed of 125 words per minute. In the most recent working test by the Postal Telegraph Company a speed of 130 words per minute was attained. When the system is running at this latter speed twelve operators are required, six at each end; at lower speeds correspondingly fewer operators are needed. Although only one perforating machine is shown in our photographic view of the apparatus, there are three actually required to produce the perforated tape fast enough to match the full capacity




DIAGRAM OF PAGE-PRINTING TELEGRAPH APPARATUS.

of the system. Mr. Murray does not claim that there is any great saving of labor, but that there is an enormous saving of wire. The cost of a single copper wire from New York to Chicago is \$60,000, and the system just described easily doubles and even trebles the capacity of the line. With regard to the increase in speed, it may be mentioned that the best Morse operators send fifty messages an hour, and as the messages average thirty words, this corresponds to a rate of twenty-five words a minute. As a matter of fact, fifteen words per minute is a fair average speed for a day's work. Working quadruplex it is good work for eight men, four at each end, to send a total of eighty words a minute; whereas by the Murray system it is possible to send 240 words per minute, or 120 words each way.

The Havana Western Railway is trying to induce planters to begin cotton growing in the Island of Cuba. It has procured a quantity of seed from Egypt and the sea island plantations of Georgia and sections of Mississippi Valley, and is having a pamphlet printed in Spanish for distribution with the seed which is to be freely given out to planters or owners along the line who are willing to experiment with the fiber. If a sufficient number plant the seed the railroad will put up a cotton gin and all the necessary machinery for the convenience of growers at convenient points. Cotton was cultivated extensively in the district fifty years ago, and to-day cotton trees 20 feet high are to be found growing wild in many parts of the district, the fiber, however, being coarse and green.

Composition of Meteorite.

In a paper lately read before the Académie des Sciences, M. Stanislas Meunier gives an account of a chemical and mineralogical examination made upon a meteorite which fell at Lançon, in the south of France. The meteorite in question weighs about a pound and a half, and is of a light ash-gray, contrasting with the deep black of the surface layer which formed upon it during its trajet through the air. Upon the body of the meteorite proper are seen a number of approximately parallel black lines which are only the outer edges of strata which traverse the mass. These strata have been formed at an early period under the influence of local heating and a resulting transformation of the rock, and are of the same character as the black surface layer recently formed by the heating of the rock due to air friction. The author finds that the density of the meteorite, taken in six portions weighing in all 50 grains, is 3.482 at 12 deg. C. He then analyzed it, first taking out the iron by means of the magnet. Of 30.8 grains which were finely pulverized in an agate mortar, the magnet took out 2.7 of iron in fine grains which were quite malleable, this being 8.8 per cent of the whole. In spite of their abundance in the mass, these grains are almost invisible on the breakage surfaces of the meteorite, but they appear very clearly when the surface is polished; under the microscope their forms are clearly seen, and these are quite remarkable. In the present case they are more compact than the granules observed in many other meteorites, and although ramified in form, they are less abundant in filaments and membranous parts embracing the rock elements. Often they present angular profiles in some parts of their contours, which likens them to crystals, especially as the angles often approach 90 degrees. These grains are found to contain nickel in the proportion of 8.2 per cent. Before analyzing the rocky portion, some tests were made to separate it from the metallic minerals of a non-magnetic character. A notable quantity of combined sulphur was found in the course of the operation, for the fine dust, when acted upon by hydrochloric acid, disengaged a considerable amount of hydrogen sulphide. By a series of reactions, 6.35 per cent of pyrrhotine was found. In the present case this pyrrhotine is in the form of very fine grains and is distributed throughout the whole mass. Besides sulphate of iron, the rock contains small black grains which are visible in certain parts of it when

viewed in thin sections; these grains, when separated, were found to consist almost exclusively of chrome iron, and its proportion is 0.54 per cent. As regards the stony or silicated part of the rock, a partial analysis was made by treating it with hydrochloric acid and thus separating it into a soluble and an insoluble part. The soluble part contained silica, manganese, iron and nickel, and is undoubtedly formed of peridot, especially as a microscopic examination of the rock in thin sections shows an abundance of this mineral in well characterized form. The insoluble part is more complex, and upon microscopic examination is considered to be a mixture of pyroxenic minerals, and especially of enstatite with a small proportion of aluminous minerals (plagioclase). The final result shows the meteorite to be composed as follows: Iron (with nickel), 8.80 per cent; pyrrhotine, 6.35; chrome iron, 0.54; enstatite (with plagioclase), 52.21; peridot (by difference), 32.10 per cent.

An incandescent electric lamp with two independent filaments is being made in this country. One of these is to be used at ordinary times, while the other, which develops much less candle power, can be employed throughout the night. As a rule, these filaments are made to give 1 candle power and 16 candle power, respectively. The change over from one filament to the other is made by turning the lamp in a screw socket. The watts per candle power required by the small filament are much greater than those of the 16 candle power filament. On this account, the life of the small filament is said to be much more than the life of the 16-candle power one.

THE NILE IRRIGATION WORKS.

One of the most beneficial effects of the English occupation of Egypt has been the attempt to restore the country to something approaching its former fruitfulness. Egypt is the Nile, and the Nile is Egypt. For several centuries this country, which during the reign of the Pharaohs was the most prosperous in the world, has remained over the greater part of its area a desert waste. When at the zenith of its power, the country was intersected in all directions with canals which irrigated the land; but in course of time the canals were filled up with the drifting sand from the desert and the country was abandoned.

The river Nile during its progress through lower Egypt gathers a vast quantity of rich sediment, which hitherto has been allowed to flow into the Mediterranean. It is estimated that billions of tons of this silt are thus wasted every year. The value of this alluvial soil alone may be estimated from the richness of the country at the Nile Delta. When Egypt was in the height of its prosperity, the Nile waters and silt were distributed over the desert, converting the sandy wastes into fertile fields.

The British government is endeavoring to resuscitate the country by storing the flood waters of the Nile and irrigating, once more, the desert lands. By this means Egypt will not only be in a position to produce sufficient cereals, cotton, etc., for her own exigencies, but will be able to supply the various markets of the world, since it will be possible to produce three crops in one season.

This conversion is being attained by the construction of large dams at different points on the river. Already two of these enormous structures are practically completed—one at Assouan and the other at Assiut. The idea is by no means modern, since a similar scheme was projected several years ago, and a tentative effort to realize it was made by some French engineers, by the construction of a dam near Cairo. This latter achievement, however, owing to the lack of care displayed in the erection of the barrier, and its instability, was practically a failure, and would have collapsed, flooding miles of the country, had it not been for the timely appearance of British engineers, who succeeded in strengthening the structure.

Egypt, however, although desperately requiring such a scheme to restore her country, owing to the lack of funds in the imperial exchequer would never have been in a position to have carried it out herself. The execution of the scheme originated with a syndicate of gentlemen in London, who propounded the idea to Sir Benjamin Baker, the well-known civil engineer, and Sir John Aird, the head of a large firm of contractors. The syndicate then approached Mr. Ernest Cassel, the well-known London financier, and he, together with Sir John Aird and Sir Benjamin Baker, hurried to Egypt, and laid their plans before the Egyptian government. After a short consultation the government approved the scheme and awarded the contract.

Surveys were then made of the river, to select the best spots at which to erect the dams. The river had previously been thoroughly surveyed by Major Willcocks, a well-known authority upon irrigation, so that the engineers were enabled to profit by the results of his work. Finally Assouan and Assiut were decided upon. Work was immediately commenced and has been continued day and night ever since. It was imperative that the work should be hurried forward with all possible speed, since when the Nile rose labor had to be stopped for several weeks, owing to the works being submerged.

The river at Assouan is over a mile in width, so that a fair estimate of the magnitude of the task may be made. The dam consists of a huge wall of granite, 60 feet in width at the top, 90 feet above low water, and a mile and a quarter in length, stretching across the river, from bank to bank. A roadway is to be constructed upon the top of the dam, which will afford a means of communication between both banks of the river. The dam is pierced by 180 huge steel sluices.

The erection of this barrier will impound over 1,000,000,000 tons of water, forming a lake which will extend up the valley of the Nile. When the sluice doors are opened while the Nile is at high water, something like 900,000 tons of water will rush through them every minute.

One effect of the construction of this dam will be the partial submersion of the historic temples of Philæ. When the scheme was originally projected, these ruins were to be entirely submerged, but an influential body of Egyptologists, headed by the late president of the British Academy, were successful in obtaining their partial preservation, so that now the ruins themselves will still be visible above high water.

The stone with which the dam has been built has been obtained from the same quarries which furnished the stone for the temples of Philæ and Cleopatra's Needle. Indeed, many of the granite blocks that have been excavated bear the marks of the Egyptian wedges that were utilized over thirty centuries ago. The work

is being carried out under the supervision of English engineers, and some 25,000 natives are engaged upon the task, working in day and night shifts of 12,500 men each. During the night the work is carried on under electric light. The laborers receive about a dollar a week for their labor, together with board accommodations, which, although it may appear a ridiculously small wage, is yet about twice as much as is generally paid.

According to the terms of the contract no money is to be paid by the Egyptian government to the contractors until the task is completed. It is estimated that the undertaking will cost \$25,000,000, and the settlement of the bill is to be spread over thirty years. The completion of the scheme will add 2,500 square miles to the crop-bearing area of Egypt, which, it is estimated, will be worth \$400,000,000 to the country.

THE HEAVENS IN MAY.

BY HENRY NORRIS RUSSELL, PH. D.

The season of eclipses has once more come round, and two of them occur in the present month, being its most remarkable astronomical events.

The first is of little account, being indeed termed not a lunar eclipse, but a lunar appulse, for the reason that the moon does not pass into the earth's shadow at all, though it grazes it closely, and its northern limb is considerably dimmed by the penumbra of the shadow. It takes place on the third and is invisible in America, but may be seen in Europe.

The second—the total solar eclipse of May 17—is a very notable one, and would doubtless be the most important one for many years, were it not for the unfortunate situation of the shadow-track, which crosses land for only a small fraction of its length, and that in rather inaccessible situations. Beginning in the Indian Ocean near the South African coast, it touches the southern end of Madagascar, passes over Mauritius, and after crossing several thousand miles of sea, falls on Sumatra and Borneo, crossing them almost exactly on the line of the equator, and moves eastward over Celebes, the Spice Islands and New Guinea, into the Pacific, where it leaves the earth.

The most favorable situations from which to observe the eclipse are on the coast of Sumatra, but unfortunately the weather conditions are bad, the chances being somewhat against clear skies at noon at this season—a poor showing compared with the ratio of six clear days to one bad one which held good for some American stations a year ago.

But the most remarkable feature of this eclipse, and the one which will cause astronomers to travel half way round the globe to see it, is its extraordinary long duration. While last year's eclipse, and the Indian eclipse of 1898, lasted at most about two minutes, the duration of totality on the present occasion is at maximum no less than 6 minutes and 26 seconds, which is longer than any that has ever been observed with modern instruments. This will add little to the importance of the phenomenon in the study of the lower layers of the sun's atmosphere, but will be of immense value for investigation of the corona, and also in the hunt for possible intra-Mercurial planets, since it enables photographic exposures of much greater length than usual to be made.

Since Americans who stay at home cannot see the eclipse, its interest for them must be chiefly theoretical; and in this connection, the question presents itself at once, "Why should this eclipse last so much longer than usual?" The principal reason is the moon's greater nearness to the earth, as we shall proceed to study in detail.

The orbit of the moon, like those of many other heavenly bodies, is decidedly eccentric, so that her distance from the earth varies by about 7 per cent on each side of the average value. Her apparent diameter is of course subject to corresponding variations, being greatest when she is nearest us. On the average it is 31' 7", but it may appear as great as 33' 32" or as small as 29' 28". The sun's apparent diameter is subject to similar changes due to the eccentricity of the earth's orbit about him. Its mean value is 32' 4", its greatest 32' 36" and its least 31' 32".

A clear understanding of the character of the different kinds of solar eclipses follows easily from the consideration of these figures. Suppose the observer to be so situated that the center of the moon appears exactly in front of that of the sun. If the moon is at her nearest she will appear larger in diameter than the sun, and will hide him completely, producing a total eclipse, while if she is at her farthest she will seem smaller than he does, so that a bright ring of uneclipsed sun will appear all round her, forming an annular eclipse. Since the average diameter of the moon is less than that of the sun, annular eclipses will evidently be more frequent in the long run than total ones.

The diameters of the sun and moon given above are those of these bodies as seen from the earth's center. But as a matter of fact they are observed from its surface, which must introduce certain modifications into our reasoning. If the observer is directly under the

body he is 4,000 miles nearer it than he would be if at the earth's center, or if on any part of the earth where the body is just rising or setting. This makes no perceptible difference in the apparent size of the sun, since 4,000 miles is less than 1/20,000 part of his distance. But the case is not the same with the moon. When she is nearest she is but 220,000 miles away, and 4,000 miles is 1/55 part of this. Since she is 1/55 part nearer to the observer than to the earth's center she must look 1/55 part larger.

Referring to the above figures we find that her diameter will be increased by 36", becoming 34' 8" as against 33' 32" as seen from the earth's center.

This augmentation of the moon's diameter increases the duration of a total eclipse, since the moon appears larger and extends farther beyond the sun's limb. It decreases the length of annular eclipses, because, since the moon seems larger, the width of the projecting rim of the sun is less. Its most remarkable result, however, is that the same eclipse may be total in one part of the earth and annular in another. Suppose, for example, that an eclipse occurs when the sun's diameter is 32' 4" and the moon's, as seen from the earth's center, is 31' 50". To an observer so situated that the moon is rising or setting, its apparent diameter will have this same value; and since the sun's is greater, he will see an annular eclipse, provided, of course, he is in the line of central eclipse. If, on the other hand, another observer, still on the line of central eclipse, has the sun—and moon—in his zenith, the moon will appear larger to him by 36" than to the first observer, on account of the augmentation, and will have an apparent diameter of 32' 26", which is 22" bigger than that of the sun, so that the eclipse for him will be total. On the 17th the sun's apparent diameter is 31' 37" and the moon's 33' 12". While the first is not quite at its minimum nor the second at its maximum this is much more nearly the case than usual, and to this circumstance the unusually long duration of totality is due.

THE HEAVENS.

We have nearly lost the winter constellations by this time. Only Auriga, the Twins and the lesser Dog-star remain, and they are so low in the west that we cannot hope to see them much longer.

Cassiopeia swings low beneath the pole, while the Great Bear is far up in the zenith above us. Draco is coming up on the eastward, almost surrounding the Little Bear with his starry coils. Cygnus is rising in the northeast, and Lyra is well up. Ophiuchus and Serpens occupy the eastern horizon, and Hercules, Corona, and Boötes extend upward nearly to the zenith, with the brilliant and ruddy Arcturus near the highest point. Of the zodiacal constellations, Leo and Virgo are conspicuous in the southwest and south. Cancer and Libra are visible on either side and Scorpio is rising in the southeast. Hydra occupies the lower southwestern sky, and low in the southeast and south are some moderately bright stars, which are all that we can ever see of the brilliant southern constellation Centaurus.

THE PLANETS.

Mercury is morning star till the 14th, when he passes behind the sun and becomes an evening star again. He can only be seen during the last few days of the month, when he sets nearly one and one-half hours later than the sun. At the time of the eclipse he will be visible close to the sun on the east, in a position singularly like that in which he was so conspicuous last May, but on the opposite side of the sun. Venus will be very close indeed to him. She is now an evening star, but will not be clearly visible in the twilight till the latter part of May. Mars is evening star, moving slowly eastward through Leo. He is in quadrature on the 28th, southing at 6 P.M. Jupiter rises about 1 A.M., Saturn about 1.15, and Uranus at about 11 P.M. in the middle of the month. The last named is in Scorpio, the other two in Sagittarius. Neptune is evening star in Taurus.

THE MOON.

Full moon occurs at the time of the lunar appulse on the afternoon of the 3d, last quarter on the forenoon of the 11th, new moon during the solar eclipse of the 17th, and so about midnight of our time, and first quarter at midnight on the 24th.

The moon is farthest from the earth on the 2d and again on the 29th, and is nearest early in the morning of the 17th, less than a day before the great eclipse. She is in conjunction with Uranus on the morning of the 6th, with Jupiter and Saturn on the afternoon of the 8th, with Mercury and Venus on the 17th, within a few minutes of each other and three hours after the eclipse, with Neptune on the morning of the 20th and with Mars on that of the 25th.

Armored Cruiser Discussion.

We are in receipt of another lengthy communication on the subject of our new armored cruisers, which will be found in the current issue of the SUPPLEMENT. Hereafter all correspondence on this subject will be transferred to the last-named publication.—Ed.


TURKISH SUBMARINE BOAT OF THE NORDENFELDT TYPE.

At the present time, when so much attention is being paid to the submarine boat, and several of this type are being constructed for our own navy, it is of interest to turn to an early series of experiments, carried out by the British Admiralty, which, in the opinion of our contemporary, *The Engineer*, to whom we are indebted for our illustrations, "has left them in such a position that there is practically nothing more to be learned on the subject from such experiments as France, going over very old ground, is now conducting."

Referring to the French experimental work now being carried on, the same authority says that between the year 1886 and September, 1888, a series of experiments in the construction and use of submarine boats was carried on in this country and abroad, beside which the French experiments now going on are mere child's play. Mr. Garrett, a gentleman in holy orders, and extremely ingenious, devoted the greater part of his life and fortune to the development of the submarine boat; and with him was associated Mr. Nordenfeldt, the inventor of the well-known Nordenfeldt gun. The vessel was designed to run near to the vessel to be attacked, then sink 20 feet below the surface, and proceed submerged to within striking distance, when she would discharge her torpedoes and return. For the purpose of propulsion steam was used in the ordinary way on the surface. When going to sink, the chimney was removed, and air-tight stopper fitted on the opening to the up-take. The furnace mouths were similarly closed by doors like those of a gas retort, and the boat sank. Power was then supplied on Lamm's system by the hot water in the boiler. The experimental boat quite realized all Mr. Garrett expected. A second boat was constructed, and after elaborate and prolonged experiments full of incident, the little vessel was bought by the Turkish government.

The accompanying illustrations show two sectional views and a view from the quarters of one of the Turkish boats, whose description and principal dimensions, as given in *The Engineer*, are as follows: Length 100 feet, beam 12 feet, and displacement 160 tons. The engines are of the ordinary surface-condensing compound type, with two cylinders, and are estimated to indicate, at a pressure of 100 pounds of steam, 250 horse-power. There is nothing particularly to remark about these engines, except that the circulating and air pumps are worked by a separate cylinder. The main engine is thus left free to work or not, while vacuum is always maintained to assist the various other engines with which the boat is fitted. The boiler, marked *G* in the longitudinal section, is of the ordinary marine return-tube type. It has two furnaces, and the heating surface is about 750 square feet. A novel feature about it is, however, that after the products of combustion have passed through the tubes, they again pass through a large pipe, marked *H*, in the steam space of the boiler before they reach the funnel. The object of this is threefold: First, the economy of heat and fuel; secondly, to enable the funnel to be as near the center of the boat as possible, and thirdly, that the inboard portion of the same might be kept the cooler by thus lengthening the passage to it of the heated air. The hot-water cistern is seen at *P*, and the power to operate all the separate engines during a submarine voyage is the heat, as previously mentioned, which is stored up in its contents, as also in those of the boiler. In all there are some 30 tons of water, the vapor of which has a maximum tension of 150 pounds per square inch when the boat is first submerged; and this, with the assistance of the vacuum, is sufficient to drive her from thirty to forty miles without lighting any fire on board or using any air for the generation of heat. The pressure is raised in the hot-water cistern as follows: Live steam from the boiler enters a series of tubes which have a superficial area, in all, of some 500 square feet, and after parting with its latent heat to the contents of the cistern, being then in the aqueous form, is taken off by a small double-acting pump and carried back


to the boiler. The propeller, *A*, is placed abaft the rudder, *B*, and it will be noticed that although the shaft is central, working on the thrust-block, *D*, the coupling connecting the crankshaft of the engine, *E*, is placed low down in the boat. It is this feature in the arrangement which admits of the use of a marine engine of ordinary type. The engines which operate the vertically-acting screws are of the three-cylinder type. This is in order that there may



CROSS-SECTION OF TURKISH SUBMARINE BOAT.

be no dead center, as it is highly important that they should start the moment steam is turned on. By the use of a special valve the captain is enabled to vary the speed of the propellers and to stop them both together or separately, at will, and thus to arrange the depth at which his craft is to operate. As seen in the engraving, these propellers in the Turkish boats are placed in the fore-and-aft line.

The maintaining of the vessel in a horizontal posi-



VERTICAL LONGITUDINAL SECTION.

tion is controlled by two bow-fins. By a very ingenious arrangement of a plumb-weight, with other mechanism extending to the conning-tower, the action of these fins is rendered both automatic and controllable, and perfect command is thus insured over the movements of the boats, as far as the vertical plane is concerned. To touch now upon the manner in which the "Nordenfeldt" is operated, it should be understood that the boat has two distinct conditions of existence

inner and outer portions of the funnel, *M* and *M'*, is not seen, it should be mentioned, in the engraving. In this position, with more or less of her bulk immersed, as may be thought necessary, according to the nature of the service upon which she is engaged, the boat can proceed upon voyages only limited in extent by her coal-carrying capacity. This in the Turkish boat is estimated to suffice for the fuel to drive her 900 knots at a moderate speed. The immersion of the

boat in her surface condition is regulated by the admission or otherwise of water into the ballast tanks. Of these there are three, one at each end and a third under the center compartment, *T T T*, in the engraving. The two first mentioned contain about fifteen tons of water each, and the central one seven, when the boat is at her proper draught for descending. At this draught there is very little of the craft visible beyond the conning tower, and knowing even in which direction to look, it is not an easy matter to make her out at any great distance, the eye being unassisted by the ear on account of the noiselessness of the engines. All those who have witnessed the running of the boat here have been particularly struck with this feature of her performance, as also the little disturbance at the surface occasioned by the screw.

Before the boat can assume her condition as a submarine craft, it is necessary to hermetically close the furnaces, which is done by the doors marked *N*, upon which combustion is soon brought to an end. The piece of funnel connecting the boiler with the out-board portion is then removed, and the doors, *O* and *O'*, placed in position, as shown in the engraving. While these changes are being effected, water is allowed to run into the ballast tanks, to reduce the buoyancy to its proper limit, and this arrived at, nothing remains but to close up the conning tower. The vertically-acting screws may then be set in motion to place the boat quite out of sight, or she may proceed with nothing but the glass cupola of the conning tower showing above the surface.

SIBERIA IN THE GLACIAL AGE.

Prof. G. Frederick Wright, of Oberlin College, recently returned from a trip around the world made in the interests of the science of geology. The main object of the trip was to settle, if possible, what has long been a disputed question among geologists—that is, whether Siberia has ever been covered with ice as North America and parts of Europe were during the glacial period. The view which is generally accepted is that Siberia was covered with ice, and a great many geologists still hold this view.


As a result of his trip Prof. Wright believes that at the time when North America was covered with ice, Siberia was covered with water. He found no signs of glacial phenomena south of the fifty-sixth degree. North of that he did not go, but he is convinced that the land was never covered by ice as was our own.

According to *The New York Sun*, Prof. Wright says:

"We did find indications of an extensive subsidence of all that region, which puts a new light on everything here. At Trebizond, on the south shore of the Black Sea, there was evidence of a depression of 700 feet. This was shown by gravel deposits on the hills. In the center of Turkestan the waters reached their greatest height, for there we found these deposits over 2,000 feet above sea-level. Southern Russia is covered with the same black earth deposit that we found in Turkestan. There were still other evidences of the waters having covered this portion of the globe. One of these is the presence yet of seals in Lake Baikal, in Siberia, 1,600 feet above sea-level. The seals which we found are of the Arctic

species, and are the same species as found in the Caspian Sea.

"The only theory, therefore, is that they were caught there when the waters receded. Perhaps the most wonderful discovery of all was at the town of Kief, on the Nippur River, where stone implements were found fifty-three feet below the black earth deposit, showing that the water came there after the age of man. This enabled us, therefore, to determine the



SUBMARINE BOAT IN DOCK AT CONSTANTINOPLE.

as a torpedo craft—that of a surface boat, and a submarine one. When performing the functions of a surface boat, the air which is sucked into the boat through the conning tower, *K*, by the fan, *L*, is forced by the said fan into the engine-room. From here, having no other outlet, it passes into the furnaces, and after supporting combustion reaches the atmosphere by way of the tube, *H*, as previously described, and the funnel. The connecting link between the

age of this depression. It shows that since man came there there has been a depression of 750 feet at Trebizond, and in southern Turkestan the waters were over 2,000 feet deep. The implements found were such as those made in North America before the glacial period, which gives good ground for believing that the depression was made there when the glacial avalanche occurred here. In short, it was practically the Flood."

Prof. Wright made some interesting investigations on the Red Sea. He states that it has hitherto been supposed that the Children of Israel crossed the Red Sea at Suez, but it has been found difficult to reconcile this supposition with the fact that a million persons crossed the sea in a single night, which would necessitate a very wide division of the waters. His explorations north of Suez have convinced him and those to whom he talked that the point of crossing was twenty miles north of Suez, because at that point the conditions are all fulfilled. The waters at that time were about four feet in depth there, and the mountains are in the west, just as related, and an east wind would have swept bare a place at least five miles wide.

HOFMAN'S FLYING MACHINE.

Following hard upon the heels of the Viennese engineer, Wilhelm Kress, whose aeroplane has been illustrated and described in the SCIENTIFIC AMERICAN, comes a Berlin inventor, Regierungsrath J. Hofman, who has constructed what is claimed to be a working model of a flying-machine. Kress, for lack of funds, was severely hampered in building his device. Unable to purchase a motor—an obstacle which, we are glad to note, has been overcome with the assistance of the Emperor of Austria—Kress could test his contrivance only on water. Hofman, on the other hand, did not immediately proceed with the building of a full-sized machine, but has first constructed a model on a scale of 1 to 10.

To start and to land are the most difficult feats in operating a flying-machine. For this reason ingenious inventors, among them Prof. Langley, have erected special frames from which they start their machines in order to secure sufficient living force, the machines themselves being merely of sufficient strength to meet the requirements of the speed to be attained. Hofman's machine differs materially from the contrivances of these inventors, in so far as he uses no particular launching-frame or other construction. He employs legs which are provided with wheels at their lower ends, and which are normally in the position shown in Fig. 2, but which are suddenly drawn from the ground close to the body when the propellers are set in motion. Robbed of its support, the machine falls, driven forward by its propellers. But the machine drops barely a second; beneath the wings, projecting far out from each side, sufficient air has collected to sustain the entire apparatus. New masses of air continually collect beneath the wings, so that, it is claimed, the buoyant force of the air becomes so great that the machine is not only supported in its flight, but is even driven further upward, there to be maintained at the desired height by the action of its propellers.

The little steam-engine used to drive the propellers is supplied with steam at a pressure of 165 pounds by a boiler composed of 72 water-tubes. The engine itself is made of steel. For a full-sized flying-machine, Hofman intends to use coal as fuel, although the firing of the boiler with petroleum has also been contemplated.

The wing or sail surfaces have an area of over 21 feet, and project laterally to a distance of 4.66 feet. The entire weight of the little model is 7.7 pounds.

The Scientific Alliance of New York city is now actively engaged in raising funds for a building to be devoted to the scientific societies of New York. It is desired to obtain \$500,000.

The White Rhinoceros.

A few individuals of the white rhinoceros, *Rhinoceros simus*, are to be found in Natal and Zululand, but their number is very small; it is supposed that not more than twenty of these animals exist in the world. Not long ago a band of five individuals was seen by a




Fig. 2.—READY TO START.

party among whom was the Governor of Natal. This was in one of the regions set apart as a game preserve, near the junction of the White and Black Umfolzi. The governor and a local functionary were told that a band of these animals was to be seen; both proceeded in the direction indicated, on horseback, and soon came in sight of the band. The animals were moving slowly toward a clump of bushes and allowed themselves to be approached, not seeming at all shy; the horsemen came within 150 feet of the




Fig. 1.—POSITION OF THE WINGS WHEN FOLDED.

enormous animals, who were occupied in feeding upon the grass of the plain, near some scattered trees. As they did not seem to be alarmed, the two men dismounted and approached on foot, stopping at a distance of only 60 feet from the group. They were thus enabled to observe the animals very closely for more than a minute; the latter did not seem to pay any attention to them, but kept on grazing. Soon, however, they commenced to sniff the air and became uneasy, but without apparently seeing their visitors,




Fig. 3.—THE HOFMAN FLYING-MACHINE IN FLIGHT.

who were not at all concealed, and then commenced to move off slowly, first walking, then at a trot. It is a rare circumstance to see and to observe these animals for any length of time at such close quarters. The group was composed of four adults, among whom was a powerful male, and an individual of three-quarters growth. On the same day were seen a group of three others of the same species, and these include

nearly all the animals of this species remaining in the region, within one or two; it is supposed that the number is not more than ten in all. It is thought that a few specimens exist also in the chain of Ubombo, but this appears doubtful, these being rather the *R. bicornis*. The white rhinoceros is protected as strictly as possible, and it is forbidden to hunt them under a penalty of \$250 to \$500, or imprisonment; the governor himself cannot give permission to kill them. It seems likely that the species will before long become extinct.

The Quagga.

The Zoologist contains an interesting account of the quagga and its disappearance, by Mr. Graham Renshaw. The quagga is now entirely exterminated, owing to its wholesale destruction by the hunters and colonists in South Africa. The blaubok has long since disappeared, and the blesbok nearly so; among other animals which are fast disappearing are the gnu, the white rhinoceros, the southern giraffe and the quagga. The latter was in former times very abundant at the Cape and in Orange Free State, and it

wandered in these regions in herds of considerable size; at present, however, not a single one is found. This animal had almost the form of a horse, as regards the mane, tail, hoofs and general proportions. Its color was red-brown, passing to a tan color at the rear, then to white on the legs, tail and abdomen. The head was striped like that of a zebra, and the neck had large stripes of dark brown and white. The quagga when captured young was easily domesticated, and it could be crossed with the horse. It could be hitched to a vehicle, and in the first half of the century some of these animals have been seen drawing carriages in Hyde Park. The species has disappeared in the course of the present century; a hundred years ago it was still very abundant, although in 1820 it had already abandoned the district of Albany at the Cape. W. C. Harris, in 1836, explored the South African region and found the quagga in abundance in the plains to the south of the Vaal; to the north it was replaced by the zebra. The different quadrupeds were quite numerous, including, besides the quagga, the gnu, the blesbok, and others. It is especially after 1850 that the quagga began to diminish in number. The Boer hunters commenced to make their appearance and killed the quagga for its hide; there was no restriction laid upon the hunting of this animal, and after a number of years it began to be killed off; in 1865 it had disappeared from the Cape, and a few years later from Orange Free State. At the present time it has entirely disappeared and it is only in a few museums that stuffed specimens are to be seen.

Among the museums possessing skins or skeletons may be mentioned those of London, Edinburgh, Philadelphia, Paris, Amsterdam, Berne, Vienna, etc., the total being twelve or fifteen skeletons and skins. This is all that remains to represent a species which was once counted by thousands.

Compromise of an Important Patent Suit.

Suits for infringement of patents instituted more than five years ago by the American Nickel Steel Company, of Philadelphia, against the Carnegie Steel Company and the United States government were compromised at Washington on April 23. The amount paid by the defendants is not known. It is said that the sum paid amounted to about 5 cents a pound for armor plate in which nickel steel was used. It is also said that suits will now be brought against other manufacturers who use nickel steel in any form. The


American Nickel Steel Company grants to the government and the Carnegie Steel Company a license to use the patents of that company in all nickel armor plate manufactured by them.

There are about forty steamers whose sole work is the laying and maintenance of the telegraph cables of the world.

A SIMPLE CAR MOVER.

When a car is to be moved a short distance and it is not convenient to use a locomotive, special hand devices are used. A simple, highly efficient device of this kind has been invented by Samuel E. Kurtz, of Sac City, Iowa.

As our illustration shows, the car-mover comprises a lever in which a fulcrum-roller is adjustably held and with which a swinging grip-hook is connected.

**KURTZ'S CAR-MOVER.**

A knife-edge on the grip-hook serves to grip the car-wheel when the lever is operated.

With the fulcrum-roller bearing on the truck-frame, powerful pressure can be brought to bear to turn the wheel. The roller moves toward or from the end of the lever to change the leverage power.

The device applies its power in the direct course of the revolution of the wheel, and every pound applied is utilized. Its construction is simple and durable. Its weight is but 20 pounds.

COMBINATION METAL AND WOOD-WORKING MACHINE.

An ingenious and inexpensive combination metal and wood-working machine has been invented by G. W. Hoadley, of Garden Grove, Iowa, which machine fills the want for some portable device by which threads can be cut on large rods or pipe. Any screw plate can be used; for no dies are required. It is one of the main features of the device that the rod or pipe and not the thread-cutting tool revolves. The machine can be used for boring metal or wood, sharpening disks or tenoning spokes.

On a bed a headstock is carried, having a bearing for a hollow shaft carrying on its inner end an adjustable pinion which is adapted to mesh with one of a number of bevel gear wheels arranged concentrically on the inner face of a multiple gear wheel (Fig. 3). The multiple gear is transversely journaled in the headstock. Collars on opposite sides of its bearing hold the hollow shaft in position but permit its longitudinal adjustment to bring the pinion in mesh with any of the bevel gears on the multiple gear. To permit this adjustment the multiple gear can be shifted outwardly. A setscrew on the outer end of the hub of the multiple gear secures a pipe or other article to be threaded and causes the pipe to rotate with the gear wheel, when a crank on the end of the hollow shaft is turned. In threading smaller pipes or rods, a collar having a setscrew is secured in the hub of the multiple gear and the pipe is secured in the collar by the setscrew. The thread-cutter is of any approved type and is provided on its stock with handles to start the thread by hand. Sockets in the cutter stock receive long handles which rest on bars or arms (Fig. 1). Thus in threading a pipe, the cutter is held rigidly in place, while the pipe is turned with the multiple gear by the rotation of the crank on the hollow shaft. If it be desired to sharpen a harrow disk, a sharpening tool carried on one of the bars of the head-stock is used. The harrow disk is mounted on the squared end of a rod secured in the hub of the multiple gear, so that the disk is rotated with the multiple gear and the disk-edge sharpened (Fig. 2).

When it is desired to use the machine in boring holes in wood or metal, or in forming tenons on spokes, as shown in Fig. 4, then the crank-arm is removed from the hollow shaft and placed on a rod or pipe secured in the hub of the multiple gear, and the end of the hollow shaft is fitted with a boring tool. Upon turning the crank-arm secured to the

multiple gear, the hollow shaft and the tool will be turned. In order to feed the tool into the wood, the wheel or other work is carried on a slide, spring-pressed into engagement with the tool.


In a shop the gearing can be permanently mounted on a bench if it be so desired, but the construction is so simple that the operative mechanism can be readily removed. The gearing can be bolted to the bottom of a pump wagon or to any convenient bed.

Manufacture of Coconut Butter in Mannheim.

The manufacture of coconut butter is an industry of some importance in Mannheim. This factory is said to be the only one of any considerable size in Germany. It has an output of about 10 tons of butter per day. The business was started in 1886, and, the proprietors say, shows a steady increase. The product is sold under the name of "Palmin"—a registered trade name—or coconut butter (German, "Kokosnussbutter"). It is manufactured from the kernels of coconuts and is used as a substitute for butter and lard in cooking. As sold, it is generally white in color, almost tasteless, melts at about 80° F., and is of about the consistency of mutton or beef tallow. When desired by consumers, as bakers, confectioners, etc., the product is colored to resemble ordinary butter. When furnished to dealers, it is unlawful to color it. The proprietors claim an analysis of their product shows it to contain more than 99 per cent of vegetable fat, with but a slight trace of water, while ordinary butter contains about 85 per cent of fat and nearly 15 per cent of water. It is stated that the substance does not become rancid easily, that it will keep for three or four months in a cool room, and that it is much more wholesome and easily digested than the ordinary fats used for baking and cooking. For this reason the product has met with considerable favor in German hospitals and other institutions, and for use in army camps.

Coconut butter is generally put up in square packages wrapped in parchment paper, a small percentage being sold in tin cans. The latter are hermetically sealed for shipment during hot weather. The product is sold at one price throughout Germany, namely, about 16 cents per pound, or about half the price of ordinary butter. It is handled in somewhat limited quantities by about fifty grocers in Mannheim.

The processes of manufacture are, for the most part, secret, and, it is claimed, are protected by patents. The kernel of the coconut is imported in thoroughly dried strips, forming the "copra" of commerce. It is subjected to various refining processes by which all the free acids and other substances are separated, leaving only the vegetable fat. In the latter stages

**COMBINATION METAL AND WOOD-WORKING MACHINE.**


of the manufacture the product resembles ordinary butter recently churned. It is placed in machines similar to the separators used in creameries, in which the water and other foreign substances are separated by centrifugal force. In the manufacture of coconut butter a by-product, consisting of free acids and other substances, is obtained and sold to soap manufacturers.

A very bright comet was discovered by Halls at Queenstown April 23. It was observed at Cape Town by Gill April 24.

A NOVEL FIFTH-WHEEL.

A wagon and carriage fifth-wheel which has a central ball-bearing and interlocking strain-relieving segmental braces forming a portion of the bearing is a recent-patented novelty, invented by Christopher G. Burdick, of Antigo, Wis.

The central ball-bearing in question comprises two cups, one arranged to enter the other. One cup has a hollow post which passes through an aperture in the opposing cup; and through the hollow post a king-bolt extends, which is provided with a washer having bearing against the cup through which the bolt is

**THE BURDICK FIFTH-WHEEL FOR WAGONS AND CARRIAGES.**

passed. Within the cups around the post balls are placed.

Extending rearwardly from the cups are segmental guards or braces, the under face of one guard having a half-round groove and the upper face of the opposing being triangular in cross-section. The two guards or braces are normally held out of contact with each other.

Should the weight be greater on one side than on the other or should the vehicle be cramped at any time, the braces or guards will be brought together in such relation that they will sustain the greater portion of the unevenly-distributed weight and will therefore prevent the ball-bearing of the fifth-wheel from being subjected to extra friction or from being cramped or locked.

The construction of the fifth-wheel is furthermore such that the main king-bolt is concealed and protected. Auxiliary king-bolts located at front and rear of the main king-bolt act in conjunction with the braces or guards to overcome the severe strain which the main king-bolt would otherwise be called upon to sustain.

Under date of February 23, 1901, Consul-General Guenther, of Frankfort, says it is reported that the Russian government, in order to facilitate the telegraphic business between Odessa and Berlin, will construct a direct line between these two cities. Work on the new line will be commenced in the spring.

The Current Supplement.

The current SUPPLEMENT, No. 1322, has many interesting and valuable articles. "How Art Is Applied to Industrial Training in Philadelphia" is by J. A. Stewart and is accompanied by a number of engravings made from photographs taken especially for the SUPPLEMENT. "Screw Barges" describes a new system in use in England. "Induction Coils and Interrupters" is accompanied by three engravings. "High Potential Phenomena" is by A. P. Carman. "Military Bridges" illustrates some interesting portable bridges, or bridges which can be constructed at short notice. "European and Asiatic Faunas and Their Relations Past and Present to that of Africa" is by Prof. H. Pilsbry. "A General Survey of Foreign Trade" is concluded in this issue and is accompanied by two maps showing the entire world and where the United States manufactured goods are sold.

Contents.

(Illustrated articles are marked with an asterisk.)

Baldwin-Ziegler expedition.....	275	Meteorites, composition of.....	278
Bridge Bill, North River.....	274	Moore, Edward B.*.....	527
"Celtic" launch of the*.....	276	Nile, irrigation works*.....	273, 279
Clock, perpetual motion*.....	276	Nitro-cellulose.....	274
Coconut butter.....	282	Patent suit, compromise of.....	281
Commissioner of Patents, Asst.*.....	275	Quagga.....	281
Exposition, Pan-American.....	275	Rhinoceros, white.....	281
Fifth-wheel.....	282	Siberia in the glacial age.....	280
Flying Machine, Hoffman's*.....	281	Smithsonian report.....	274
Heavens in May.....	279	Submarine boat, Turkish*.....	280
Inventions recently patented.....	283	Telegraph, page-printing*.....	277
Machine, metal and wood*.....	282	Wine production, French.....	277

RECENTLY PATENTED INVENTIONS.

Agricultural Implements.

MACHINE FOR TOPPING BEETS.—JULIUS H. LUHRS, Fruita, Col. This machine for topping beets is so constructed that the cutters will remove the same amount of crown from the beets, whether the crowns be just above the surface of the ground or extend some distance above the surface. The machine is light and strong and is provided with means whereby the cutting section will automatically adjust itself to the exposed portions of the beets in its path, so that the crowns will be cut at a uniform depth.

Engineering Improvements.

STEAM-BOILER.—CHARLES EDGERTON, Fidelity Building, Philadelphia, Pa. Above the crown-sheet of this upright tubular boiler a receptacle is placed for catching and retaining scale, the receptacle being of less diameter than the shell of the boiler. All the tubes pass through this receptacle so closely that no water-circulating opening is provided. A handhole and cover are arranged within the shell of the boiler at or near the level of the receptacle. Upturned edges of the receptacle prevent the discharge of the scale over the edges into the water-leg. The upward circulation is confined entirely to the annular space surrounding the pan, which insures the precipitation of the sedimentary matter toward the center. By reason of this construction the crown-sheet of the vertical tubular boiler is rendered more durable.

Mechanical Devices.

COUNTERBALANCE.—ROBERT E. FORD, Pasadena, Cal. The invention relates to machines having reciprocating and revolving parts, especially such machines in which reciprocating is to be converted into rotary motion, or *vice versa*. The principal feature of the invention consists in counterbalancing both the horizontal and vertical forces of the machine by the use of a number of counterbalancing bodies, arranged to move in unison, to counterbalance one another in a vertical direction, and to revolve in unison with the revolving parts of the machine. The bodies have an aggregate mass and center-of-gravity radius such that the product shall be equal to the product of the mass of the reciprocating parts and the crank radius.

PROPELLING VESSELS.—JOHN G. PINKERT, Hamburg, Germany. A new and improved motor has been devised by the inventor, operated by the explosion of combustible material for the propulsion of all kinds of vessels. In this motor the gaseous products of combustion are made to act directly upon the water or other medium to drive the vessel forward by reaction without any other propelling means. The motor has a working-cylinder open at one end in order to allow the explosion gases to act on the medium through which the vessel is traveling. A piston is moved within the cylinder. Mechanism controlled by the piston admits propelling charges to the cylinder.

DEVICE FOR OPERATING THEATRICAL SCENERY.—RICHARD HYDE, Brooklyn, New York city. The main purpose of the invention is to obviate the difficulty experienced in adjusting scenery when operated by ropes and pulleys—a difficulty caused by the expansion and contraction of the separate hanging ropes. In the present invention only the expansion or contraction of a central rope need be considered. By this arrangement scenes can be adjusted by pulling down one corner of the scene itself, the other corner going up correspondingly. The invention further provides a snap-catch for the pulley-block with which all the ropes are connected. The scenery can be lowered without the use of a counterweight.

MAGAZINE-PISTOL.—WALTER J. TURNBULL, New Orleans, La. By means of the construction provided by this inventor the cartridges are fed accurately by the same device which operates the hammer. The device also effects a positive lock for the feed mechanism, just before and during the time the hammer acts upon a cartridge. A portion of this hammer-operating mechanism is always in engagement and in controlling contact with the feed mechanism.

Railway Appliances.

PNEUMATIC PACKAGE-HOLDER.—GEORGE H. WALL, Cadillac, Mich. The invention is a drop-platform for railway-cars and other vehicles employed to carry freight parcels, mail matter, and the like. The platform can be raised and locked, but is free to drop when released by the locking device, either by its own weight or by the weight of material placed thereon. The means employed for raising the platform permit the handling of a heavy load. The devices for raising the platform are pneumatic and operate with the least possible friction.

Miscellaneous Inventions.

JUNCTION-BOX.—GEORGE L. HOLSHUH, Brooklyn, New York city. The invention is an improvement in junction-boxes for electric wiring in buildings and provides a ceiling junction-box with a simple device for locking it to a gas-pipe, the device being conveniently operated by a tool inserted through an opening in the lower side of the box.

HARNES ATTACHMENT.—ORANGE A. DEAN and CHARLES H. ADREAN, Toulon, Ill. The attachment is designed to hold a check-

rein in engagement with the gig-saddle and to hold the pad in place. The gig-saddle is provided with a check-hook. Under the gig-saddle a flexible strap lies, comprising a shank provided at one end with a loop capable of being bent upward to receive the checkrein and at the other end with an eye capable of being bent upward to engage the back-strap.

CUSPIDOR.—JOHN C. BLAIR, 40 Chestnut Street Louisville, Ky. A water-pipe is arranged within the cuspidor and is passed centrally through a disk. A flanged spreader is connected with the pipe and has lateral orifices opening below the flange and above the disk. A central screw-valve is arranged in the spreader, its head being accessible at the top of the spreader. The sanitary merits of this arrangement need no comment.

STEAM AND HEAT CONSERVATOR.—BARDEN W. TAYLOR, Manhattan, New York city. One object of the invention is to condense the exhaust-steam and utilize its heat for reheating and superheating the water of condensation and for heating air to be used in the firebox. Still another object of the invention is to purify the water of condensation and form feed-water free from all foreign matter, liable to produce scale in the boiler.

METHOD OF TREATMENT OF AMALGAM CONTAINING COPPER OR PRECIOUS METALS.—JOACHIM H. BURFELD, Salt Lake City, Utah. The method of treating amalgams which forms the subject of this invention consists in adding sulfur to the amalgam at a temperature not exceeding the boiling-point of water and separating from the amalgam the copper sulfid formed.

THEATRICAL DEVICE.—SAMUEL W. COMBS, Manhattan, New York city. The purpose of the invention is to provide a stage effect in which water apparently rises gradually to a certain level on the stage, but without wetting the stage. A glass tank is employed which is used in connection with a tarpaulin or water-proof cloth to produce the illusion that the stage is being gradually covered with water. These tanks are so placed upon the stage that the sides toward the audience being transparent, cannot be seen, the horizon lines being properly concealed by stage fittings or settings of any kind. Any action that may take place behind the tanks will be quite apparent in front.

GAGE.—ARTHUR J. LUCY, Meadowcroft, Penn Road, Croydon, Surrey, England. The gage is a workshop instrument for marking off and setting out centers, the teeth of wheels, and the like, gaging and testing bevels, setting and adjusting tools. The instrument consists of a stock, a sector circularly adjustable in the plane of the stock and designed to act as a carrier for a rule slidably fitted therein, which by the circular adjustment of the sector can be brought into any desired angular relation to the base or other datum edge of the stock. The sector and stock are provided with scales whereon this angular relation may be read off.

HITCHING DEVICE.—PARKER M. BRAGUNIER, Denver, Colo. The hitching device for the driving reins of harness is to be attached to the cross-bar of vehicle-shafts. The single or double trees are constructed in pivotally-connected sections, so that when a driving-rein is secured to the hitching device, and the sections of the single or double tree are free to move forward at their outer ends, the traces will be slackened and the draft of the vehicle will be through the reins, thus tending to check the animal should he endeavor to run away.

METAL CEILING.—FREDERICK H. S. HAWLEY, Pretoria, South African Republic. The invention so simplifies and cheapens the work of erecting metal ceilings that the plates or panels can be quickly and systematically laid upon a foundation consisting of two series of furring strips, one series being at angles to the other series and the upper series resting upon the upper surfaces of the furring strips of the lower series. Thus, it is no longer necessary to recess and interlock the strips.

DOG-MUZZLE.—WILLIAM MC MANUS and CHARLES N. DILATUSH, Hagerman, Idaho. The dog-muzzle has a body, the front part of which is extended forwardly under the mouth of the dog to prevent the dog's taking food. The body is held in position by a strap which passes over the head and is fastened to a neck-strap. The device is particularly intended for use on sheep dogs in the West, in which districts the sheep ranges are poisoned to exterminate coyotes.

Designs.

BELT.—LOUIS SANDERS, Brooklyn, New York city. The leading feature of the design is to be found in diverging points extending above and below the longitudinal edges of the body section of the belt at the back, producing a bodice effect at the rear central portion of the belt.

BUTTON.—MOSES B. SHANTZ, Rochester, N. Y. The obverse of the button has a spherical center with connected apertures and is surrounded by a circular rim arched in cross section to form at its inner edge a circular joint. The outer portion of the rim is rounded off to the reverse of the button. At its middle portion this reverse is convex and is slightly dishd to the rounded edge of the rim.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

Business and Personal Wants.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send your name and address to the party desiring the information. **In every case it is necessary to give the number of the inquiry.**

MUNN & CO.

Marine Iron Works. Chicago. Catalogue free.
Inquiry No. 505.—For small rotary pumps for moving the circulating water in gas engines.
 "U. S." Metal Polish. Indianapolis. Samples free.
Inquiry No. 506.—For lightning rod fixtures.
 Motor Vehicles, Duryea Power Co., Reading, Penn.
Inquiry No. 507.—For parties to make special needles from drawings, etc.
 WATER WHEELS. Alcott & Co., Mt. Holly, N. J.
Inquiry No. 508.—For information as to photographic paper-coating machinery.
 Yankee Notions. Waterbury Button Co., Waterbury, Ct.
Inquiry No. 509.—For manufacturers of a machine for printing, developing, fixing and washing bromide paper from a continuous roll of paper.
 La Porte Watch School, La Porte Ind. Catalogue free.
Inquiry No. 510.—For a device for burning garbage in private houses.
 For bridge erecting engines. J. S. Mundy, Newark, N. J.
Inquiry No. 511.—For spring motor fans.
 Dies & Special Machinery. Amer. Hdw. Mfg. Co., Ottawa, Ill.
Inquiry No. 512.—For manufacturers of feather renovating machines.
 Machine chain of all kinds. A. H. Bliss & Co. North Attleboro, Mass.
Inquiry No. 513.—For manufacturers of soft Swedish iron for making small magnets.
 Handle & Spoke Mch. Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.
Inquiry No. 514.—For second-hand machinery dealers handling a 9-inch acrew cutting, foot power lathe.
 Sheet Metal Stamping: difficult forms a specialty. The Crosby Company, Buffalo, N. Y.
Inquiry No. 515.—For set of castings 1 h. p. marine gasoline engine.
 Sawmill machinery and outfits manufactured by the Lane Mfg. Co., Box 13, Montpelier, Vt.
Inquiry No. 516.—For manufacturers of seamless tubing having inside diameters from 4-16 to 6-16 inch, nesting and closely fitting the next size larger.
 Our number 4 Catalogue of Automobile parts, write us, Standard Welding Co., Cleveland Ohio.
Inquiry No. 517.—For machinery for drying fruits and vegetables.
 Rigs that Run. Hydrocarbon system. Write St. Louis Motor Carriage Co., St. Louis, Mo.
Inquiry No. 518.—For a filter to filter and clarify vegetable oils.
 SAWMILLS.—Variable friction feed. Send for Catalogue B. Geo. S. Comstock, Mechanicsburg, Pa.
Inquiry No. 519.—For manufacturers of the Serpentine boiler.
 Ten days' trial given on Daus' Tip 'Top Duplicator. Felix Daus Duplicator Co., 5 Hanover St., N. Y. city.
Inquiry No. 520.—For a machine for making ice in small quantities adapted for hotel and family use.
 Machinery designed and constructed. Gear cutting. The Garvin Machine Co., 149 Varick, cor. Spring Sts., N. Y.
Inquiry No. 521.—For manufacturers of springs similar to clock springs 50 or 60 feet long, 1/4 inch wide by 45 minims thick.
 For sale and introduction in Scandinavia, of American goods, any and all. Apply to O. P. Jespersen and Sonner, Copenhagen, Denmark.
Inquiry No. 522.—For dealers in ornamental baskets made by Indians in Canada.
 The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 138th Street, New York.
Inquiry No. 523.—For machine for carding hair for mattresses.
 The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail \$4. Munn & Co., publishers, 361 Broadway, N. Y.
Inquiry No. 524.—For parties to make a combination watch charm and match lighter.
 Sheet Metal Novelties, Articles and Stampings of all sizes. Tools and dies manufactured on contract. Address Standard Stamping Co. Cor. 7th & Hudson Sts., Buffalo, N. Y. U. S. A.
Inquiry No. 525.—For manufacturers of type-writer ribbons before they are inked.
 FOR SALE.—Patent of Saw-Mitering Device, a combination folding tool. Bisection all angles automatically. Meters plain, circular, segmental and radial work. James Lumsden, P. O. Box 72, North Tarrytown, N. Y.
Inquiry No. 526.—For manufacturers of the oscillating steam engines or castings of them.
 Moistener and Sealer. For moistening and sealing stamps, Envelopes and Labels. Patents for sale or on royalty. Excellent chance for manufacturer with facilities for introducing a useful device. Address. CHAS. L. VOSE, Westerly, R. I.
Inquiry No. 527.—For manufacturers of Monarch wire cutters.
 WANTED.—An experienced specification writer and patent expert having a thorough knowledge of the patent practice and preferably one competent to handle electrical cases. Munn & Co., Solicitors, Office of SCIENTIFIC AMERICAN, 361 Broadway, New York.
Inquiry No. 528.—For the makers of the "Becker routing machine."
 HELP WANTED.—By a manufacturer in Central New York, a thoroughly competent man to take charge of woodworking department, running on hard and soft wood parts for agricultural machinery. Must have had practical experience with modern machinery and in the handling of a large number of men. State experience, age and give reference. Address Foreman, P. O. Box 773, N. Y.
Inquiry No. 529.—For manufacturers of small nails or hooks such as are driven into kegs to keep the hoops on, and are short enough to not reach through the wood.
 HELP WANTED.—By a manufacturer in Central New York, a competent man to take charge of pattern Department, making both wood and metal patterns. A man who has had charge of metal pattern work for malleable iron foundries and who understands the economical finishing and gaging of patterns preferred. Give age, experience and references. Address Pattern Maker, P. O. Box 773, N. Y.

Patent for Sale.—American rights to patented pocket warmer. A pronounced success in England. Strongly recommended by the medical profession. Easy to manufacture. Sell on sight. Profit large. W. H. Thomassen, 417 W. 22d St., New York.

Inquiry No. 530.—For information as to the process of lead burning.

Inquiry No. 531.—For manufacturers and dealers in foot power machinery, such as used by lapidarians.

Inquiry No. 532.—For manufacturers of cork-making machinery to be operated by power.

Inquiry No. 533.—For manufacturers to make small stampings.

Inquiry No. 534.—For the manufacturers of "Hawk Brand tool steel."

Inquiry No. 535.—For dealers in Crookes bulbs.

Inquiry No. 536.—For a mechanical digger or plow in combination with a traction engine to be used in wheat sowing.

Inquiry No. 537.—For good and cheap wind engines.

Inquiry No. 538.—For manufacturers of paper fiber suitable for trunks.

Inquiry No. 539.—For manufacturers of stills for the distillation of water on a commercial basis.

Inquiry No. 540.—For manufacturers of trunks and bags and tools for the making of the same.

Inquiry No. 541.—For manufacturers of trunk and bag trimmings, hinges, locks, covering, etc.

Inquiry No. 542.—For dealers in or parties to make a seamless bag such as is used by salt and sugar works.

Inquiry No. 543.—For manufacturers of lime burners to burn a substance in a powdered form.

Inquiry No. 544.—For manufacturers of milk pails.

Inquiry No. 545.—For manufacturers of novelties.

Inquiry No. 546.—For summer resort attraction such as "Shoot the Chute," "Steepchase," "Dante's Inferno," "Merry-go-rounds," etc.

Inquiry No. 547.—For a water fountain and figure for a New York village.

Inquiry No. 548.—For machine for engraving monograms and initials on glass or chinaware, not by grinding.

Inquiry No. 549.—For a process for treating iron castings to prevent rusting; not galvanizing or plating.

Inquiry No. 550.—For machinery for alluvial placer work; also for underground gold-extracting machinery.

Notes & Queries

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication. References to former articles or answers should give date of paper and page or number of question. Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn. Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same. Special Written Information on matters of personal rather than general interest cannot be expected without remuneration. Scientific American Supplements referred to may be had at the office. Price 10 cents each. Books referred to promptly supplied on receipt of price. Minerals sent for examination should be distinctly marked or labeled.

(8172) L. W. says: 1. If heat under pressure enveloped a boiler, the temperature being maintained, would its steaming power be increased, and if so what is the proportion of the pressure to the heating power? A. Yes. The heat would be imparted to the boiler if its temperature should be greater than the temperature of the boiler. The pressure depends upon the kind of material used to convey the heat. 2. What is the proportion of the increase in volume of air under increased temperature? A. Air expands by heat in the ratio of the absolute temperature. The absolute temperature below zero Fahr. is 460°, to which add the higher temperature and divide by the initial temperature, plus 460°. Thus the absolute temperature of 50° is 510°, and if the air is heated to 200° the absolute temperature will be 660°, and 660/510 = 1.294 the new volume. 3. Could hot, or expanded, air be practically employed as a motive power? A. Air expanded by heat is used as a motive power in hot-air engines. 4. What is the temperature about of a briskly burning hard coal fire? A. Temperature of a strong coal fire is from 2,000° to 2,500° Fahr. 5. What is the greatest temperature obtainable from the flame of a kerosene lamp? A. Temperature of a kerosene lamp is from 1,600° to 1,800° Fahr.

(8173) C. C. S. asks: How is it possible for the different phonograph companies to make such loud records? I have experimented with all kinds of machines, but cannot make one anywhere near as loud as I can buy. I think electricity is used to record the sound waves. A. It is not at all strange that a man whose trade it is to make records can make louder ones than an amateur can. We are not informed as to the secret process employed by different companies to make better records than their competitors.

(8174) J. H. White writes: I have seen an account of a supposed suck-hole in a certain creek in Kentucky, which upon investigation proved to be a huge lodestone, about fifty yards long and six inches wide, from which men were rescued with difficulty while swimming, and which held dogs with such power that they never came up. If this is true, is it not a manifestation of a force radically different from electro-magnetism? Can you explain the phenomenon? Will you please inform me where I can purchase a lodestone? A. If this is true, it is indeed unlike anything hitherto known on earth. No lodestone ever had any power to attract the human or canine

body. We cannot offer any suggestion in explanation till the report is found to be true. Lodestone is an ore of iron which exists in great quantities in our country, and can be bought of any dealer in specimens of minerals. You can find plenty of specimens at the university in your city.

(8175) J. H. Tripp asks: What is meant by "weight per mile ohm"? We find this expression repeatedly used in wire catalogues, as: Weight per mile per ohm, 5,500 to 5,800 pounds. A. That a wire one mile long and having a resistance of one ohm would have the weight given.

(8176) W. M. M. writes: I claim that the direction of armature of a multiple-connected motor cannot be changed by simply reversing the direction of current through the armature; but direction of armature can be changed only by reversing direction of current through the field. A. The direction of rotation of an armature is reversed by reversing the current through either the field or armature, but not through both.

(8177) C. T. P. asks: 1. What are "electric gases" in connection with boiler explosions? A. If gases from the decomposition of water accumulated in a steam boiler, they might be called "electrical gases." We have no personal knowledge of the formation of any such gases. 2. Is it dangerous to ground a telephone wire on a pipe running to a steam boiler? A. We can see no reason why it should be. 3. Would it be dangerous to put copper rivets or copper pipe connections on a boiler or on a digester for boiling fats with lime under 120 pounds pressure? A. There are in some fats acids which will act upon copper and form compounds at the expense of the copper. Thus the tube would be eaten away and in time become weak. It might then burst from the excess of pressure above what it could stand. 4. Would the copper against iron form electricity and dangerous "electric gases"? We have academic information that they will, but have been unable to find any practical engineer who will concede that there is anything in it. A. We do not apprehend anything of the kind is likely to happen.

(8178) O. P. McK. asks: Is there such a thing as electro-plating copper plates with a steel plating, or is there any plating for copper that it harder than copper itself? A. The operation called "steeling" is really coating a softer metal with iron. There are several metals harder than copper which can be deposited upon a surface of copper. The processes are given in Langbein's "Electro-Deposition of Metals," price \$4 by mail, a full and reliable treatise on the subject.

(8179) W. M. D. asks: 1. What is the cost of magnetizing steel blocks 1 x 1/2 inch, and how long will they keep their strength? A. Steel magnets are best made by sending a current of electricity around them. Make a coil of wire large enough to pass the bars through and connect to a battery. Pass the bar to and fro several times through the coil. If properly taken care of, the magnetism will be retained. See SCIENTIFIC AMERICAN, Vol. LX., No. 16, price ten cents by mail. 2. Is there any way to register daylight? A. There are several forms of sunshine recorder in use. Any of these will give the time during which the sun has shone while it has been exposed. See SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 277, 336, 369, 554, 662, 1156, price ten cents each, for illustrated descriptions of these instruments.

(8180) J. G. Von H. asks: 1. How large a spark from a spark coil is it necessary to have to excite a wire, say 1,000 feet away, with the Hertzian wave as used in wireless telegraphy? A. A Ruhmkorff coil is required for wireless telegraphy. While exact data are not at hand, it is probably near the truth that a spark coil giving a spark of one-half inch in length will transmit 1,000 feet. 2. Will a disruptive spark from a static machine excite a distant wire like the spark from a spark coil? A. A static machine may be used as a transmitter.

(8181) F. H. P. asks: Will you please state in the inquiry column directions for making an electrical heater? The system is the Edison three-wire, direct current, 110 volts at half ampere. A. If you wish but one-half an ampere to flow through your heater, it will not have much heating power. However, to make it, take about 625 feet of No. 26 iron wire and arrange it so that the turns do not touch each other. They must not touch anything which can be set on fire nor rest on any metal at any point. Asbestos is used to prevent the wire from coming in contact with the metal frame which must be used to support the wire.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued for the Week Ending

APRIL 23, 1901,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Abbrading machine, J. M. Nash..... 672,511
Accumulator battery, P. Marino..... 672,563

"Star" Lathes
Foot and Power Screw Cutting
Automatic Cross Feed
FOR FINE, ACCURATE WORK
Send for Catalogue B.
SENECA FALLS MFG. CO.
695 Water Street,
Seneca Falls, N. Y., U. S. A.

ENGINE & FOOT MACHINE SHOP OUTFITS, LATHES, TOOLS AND SUPPLIES
SEBASTIAN LATHES CO. CINCINNATI, O.

FOR LIGHT AND MEDIUM WORK
this new 14 inch
B. F. BARNES
Upright Drill is several laps ahead of any other drill on the track. It will drill from 1/16 of an inch up to 1/2 of an inch and is a strong, well built, durable tool.
It doesn't cost a whole lot either. Details are yours for the asking.
B. F. BARNES COMPANY, Rockford, Ill.

Prices reduced for Spring & Summer
Jaeger UNDERWEAR
PURE WOOL
Send for Illustrated Catalogue.
New York: 16 West 23d St.
Brooklyn: 157 Broadway
Boston: 504 Fulton St.
Philadelphia: 109 Tremont St.
Chicago: 924 Chestnut St.
82 State St.

A Tool Inventory
so comprehensive that it includes most every tool at present used by all trades and professions is
Montgomery & Co.'s Tool Catalogue
a book of 510 pages, illustrated, well printed, pocket size, and mailed to any address on receipt of 25 cents.
MONTGOMERY & CO., 105 Fulton St., N. Y. City.

State size and amount of
WROUGHT PIPE
wanted and we will quote prices. It costs you nothing and may save you much. We ship stock quoted promptly and therefore make prices only on exact specifications. **AERMOTOR CO., Chicago Heights, Ill.**

CREST MFG. CO. CAMBRIDGEPORT, MASS.
3 to 5 H. P. MOTORS
CREST Sparking Plug
CREST Coils
CREST Batteries
CREST Carburetors

Acetylene Gas Lighting
Reduced to the most Efficient, Safest, Simple and Economical Use.
We guarantee our machines perfectly automatic in action to extract all the gas from the carbide, and absolutely no over production or loss of gas. Approved by the various Boards of Fire Underwriters. Standard sizes 1 to 50 lights. Exclusive territory given to responsible agents. Correspond with
NIAGARA FALLS ACETYLENE GAS MACHINE CO., Niagara Falls, N. Y. and Canada.

NICKEL AND Electro-Plating Apparatus and Material
THE **Hanson & VanWinkle Co.,**
Newark, N. J.
136 Liberty St., N. Y.
30 & 32 S. Canal St. Chicago.

BICYCLE TIRE REPAIRING.—THE
Mending of Single Tube Tires.—A practical a tie illustrating the method of inserting patches and plugs with pliers and pluggers, together with rubber band plugging and the use of puncture bands. 9 illustrations. Contained in SUPPLEMENT 1102. Price 10 cents. For sale by Munn & Co. and all newsdealers.

Special Machinery, Dies and Coals.
Sub-Press-Dies
For Punching and Forming Sheet Metal, A SPECIALTY.
GEO. M. CRISWOLD,
New Works, Griswold Building,
33-35-37 Union St.,
NEW HAVEN, CONN.

Amalgamator, L. Mayhew.....	672,739	672,740
Amalgamator, Ghiglieri & Schofield.....	672,524	
Antirattler and thill coupling, combined, E. Jarrell.....	672,775	
Anvil, O. P. Wilcox.....	672,580	
Automobile driving gear, P. Steinhauer.....	672,718	
Axle fastening, C. Kuchenbrod.....	672,560	
Axle spindle, wagon, H. Stockman.....	672,906	
Back pedaling brake, C. O. Barnes.....	672,610	
Bag. See Laundry bag.		
Baling press, J. S. Tuttle, et al.....	672,687	
Balls, etc., machine for manufacturing, J. Bornemann.....	672,664	
Basin casing and cover, catch, J. Banwell.....	672,868	
Bearing and boxing, roller, Wood & Douglass.....	672,659	
Bearing, lubricating, P. Thomke.....	672,462	
Bearing, roller, Wood & Douglass.....	672,660	
Bed crib attachment, J. E. Hawkins.....	672,766	
Bed, folding, L. W. Welch.....	672,813	
Bed, sofa, N. P. Bradish.....	672,612	
Bed spring, A. M. Sorey.....	672,863	
Bedstead, E. M. Antisdell.....	672,867	
Berth, self leveling, J. H. & E. F. Porter.....	672,842	
Bicycle frame, A. Mayerson.....	672,738	
Bicycle package carrier, C. W. Smith.....	672,495	
Bicycle pedal, L. A. Braddock.....	672,698	
Bicycle saddle, P. V. Tillinghast.....	672,656	
Bicycles, attachment for carrying rides, etc., on, G. T. Speir.....	672,540	
Billets, manufacture of, W. B. Hughes.....	672,773	
Billiard cue, H. E. Mereness, Jr.....	672,646	
Blind, window, S. Smith.....	672,574	
Blower or pump, E. A. Osborne.....	672,803	
Boiler flue cleaner, A. Gronwald.....	672,733	
Boiler furnace, steam, W. Kent.....	672,781	
Bolt cutter, S. S. Bolsinger.....	672,869	
Boots or shoes, machine for assembling inner soles, uppers, linings, and counters of, C. W. King.....	672,624	
Bottle stopper, measuring, T. N. Jayne.....	672,850	
Bottling establishments, device for hoisting and transferring bottled beer in, Lieber & Meimberg.....	612,788	
Boutonniere, T. L. McCormack.....	672,797	
Box and floor, combined, C. O. Wickersham.....	672,725	
Brake applying mechanism, A. Flowers.....	672,758	
Bridge, revolving lift, J. P. Cowing.....	672,848	
Broom holder, R. L. Edwards.....	672,599	
Bucket, W. Benzling.....	672,520	
Bucket and hoop therefor, C. S. Reams.....	672,805	
Buggy seat, E. A. Gregory.....	672,550	
Building ventilator, C. H. Miller.....	672,488	
Bundle carrier, W. H. Moore.....	672,857	
Button, collar or cuff, G. B. Green.....	672,619	
Caisson, W. H. McFadden.....	672,858	
Calendar and advertising device, combined, J. Fulmer.....	672,549	
Calipers, E. Raus.....	672,493	
Camera-holder, W. V. Esmond.....	672,703	
Can capping machine, C. L. Baender.....	672,749	
Can closure, milk, E. Mills, Jr.....	672,791	
Cane loading machine, J. D. Martinez.....	672,789	
Car, compartment, J. B. Strauss.....	672,864	
Car, railway, L. G. Montony.....	672,561	
Car side bearing, H. M. Perry.....	672,648	
Car wheel, C. E. Varnow, A. J. Lustig.....	672,812	
Carburetor, W. S. Johnson.....	672,507	
Carburetor, J. M. Goldsmith.....	672,854	
Cardboard or pasteboard box, F. T. Austin.....	672,726	
Card cutting machine, D. E. Hunter.....	672,526	
Card trays together, device for handling several, W. S. Dodd.....	672,522	
Cards, etc., adjustable partition holder for, C. V. Styles.....	672,686	
Cards, etc., feeding mechanism for, D. E. Hunter.....	672,529	
Carding engines, apparatus for stripping revolving flats of, Jones & Heaps.....	672,674	
Carpet sweeper, device for attaching handles to, J. W. Shanahan.....	672,810	
Carriage, horseless, E. Sanchis.....	672,713	
Carrier. See Bundle carrier.		
Cartridge, W. M. Ryan.....	672,514	
Cash registering machine, J. Perrott.....	672,491	
Caster, Neuharth & Ill.....	672,506	
Casting ingots, means for, A. J. Lustig.....	672,447	
Catafalque, folding, A. M. Smitz.....	672,811	
Catapult, Bachman & Fisher.....	672,434	
Chain, L. E. Jacobus.....	672,774	
Chamber vessel, H. Hincley.....	672,483	
Change maker, S. T. Fisk.....	672,618	
Cigarette machine, G. A. Jasmatzl.....	672,776	
Cigarette mouthpiece applying machine, J. S. Beeman.....	672,472	
Claap, C. E. Mixer.....	672,703	
Clasp, C. A. Barrows.....	672,815	
Cleaner, W. H. Anderson.....	672,584	
Closet cistern and valve therefor, G. W. Wilkes.....	672,468	
Closure, F. H. Smith.....	672,862	
Cloth board, A. M. Chaffee.....	672,590	
Clothes line holder, H. Hafker.....	672,763	
Coating with molten metal, apparatus for handling sheet metal plates during the process of, J. Baxter et al.....	672,663	
Cock ball, F. F. Flagg.....	672,835	
Cocks, valves, etc., arrangement for operating, Feldmann & Korach.....	672,600	
Coffee or tea pot, E. Landvoigt.....	672,446	
Coin controlled mechanism, W. H. Pumphrey.....	672,807	
Comb cleaner, C. Fleming, Jr.....	672,757	
Combining machine attachment, cotton, H. Tunstall.....	672,578	
Combining machine, dabbng brush mechanism, Layland & Whitehead.....	672,786	
Commutator brush and brush holder, R. Lundell.....	672,604	
Commutators, means for protecting, A. D. Baldwin.....	672,727	
Conceave, J. N. Kallor.....	672,558	
Condenser, exhaust head, R. Wetherill.....	672,579	
Conduit capping, interior, W. F. Bossert.....	672,589	
Copy holder, W. J. Burt.....	672,750	
Copying press, dampener, roller, G. G. Hoffman.....	672,484	
Corkscrew, J. R. Murphy.....	672,796	
Corn husking and shredding machine, A. Van Ness.....	672,501	
Cotton press, cylindrical, W. G. Long.....	672,562	
Couch and chair, combined folding, A. Grenier.....	672,602	
Crane, traveling, F. W. Tammatt-Walker.....	672,577	
Crate, shipping, J. C. Jontgen.....	672,735	
Cream separator, centrifugal, T. C. Robertson et al.....	672,494	
Cultivator disk, J. R. Newton.....	672,536	
Curtain and blind support, combination, W. Coss.....	672,440	
Door fastener, A. Burson.....	672,439	
Door securer, M. B. Brooks.....	672,473	
Drill. See Grain drill.		
Drill casing extractor, Wilson & Loy.....	672,814	
Dye and making same, wool, K. Schirmacher.....	672,714	
Dyeing, etc., apparatus for, W. Mather.....	672,645	
Eccentric, C. Linstrom.....	672,643	
Electric distribution system, Hubbard & Chamberlain.....	672,603	
Electric light apparatus, D. M. Moore.....	672,452	
Electric light vacuum tube, D. M. Moore.....	672,451	
Electric lighting system for railway cars, J. W. Guilloit.....	672,877	
Electric lighting system for railway trains, J. W. Guilloit.....	672,878	
Electric switch, J. Reid, Jr.....	672,513	
Electrical conductor, W. A. Markey.....	672,449	
Electrical switch, W. F. Bossert.....	672,588	
Electrical transmission of motion for steering ships, etc., H. A. Spiller.....	672,851	
Electrodynamic propulsion system, L. Rosenfeld et al.....	672,712	
Electrotherapeutic machine, coin controlled, W. S. Rosley.....	672,665	
Elevator. See Hay elevator. Portable elevator.		
End gate, F. M. Sturgis.....	672,720	
Engines, means for preventing back firing in internal combustion, G. H. Lloyd.....	672,508	
Engines, oil pump for explosive, Frith & Macpherson.....	672,477	
Engines, sparking igniter for explosive, A. Rath.....	672,875	
Engines, vaporizing device for crude oil explosive, F. Van Duzen.....	672,500	
Extractor. See Casing extractor. Pen extractor.		
Feed water heater, W. L. Hill.....	672,555	
Feed water heater and purifier, J. E. Schlieper.....	672,460	

(Continued on page 285)

AUTOMOBILE PARTS.
IF YOU ARE BUILDING AN AUTOMOBILE, WE CAN SUPPLY YOU WITH PARTS AND FITTINGS.
IN OUR SEVEN FACTORIES WE MAKE RUNNING GEARS, TOOL STEEL BALLS, STEEL RIMS, STEEL STAMPINGS, CHAINS, SHEET STEEL AND FORGINGS.
ALL FOR AUTOMOBILE CONSTRUCTION.
QUOTATIONS ON APPLICATION.
THE AUTOMOBILE & CYCLE PARTS CO.
CLEVELAND, OHIO.

American Sheet Steel Company
Battery Park Building
New York
Manufacturers of all varieties of Iron and Steel Sheets
Black and Galvanized
Plain and Painted
Flat, Corrugated and "V" Crimped

Apollo Best Bloom Galvanized Sheets
W. Dewees Wood Company's
Planished Iron
W. Dewees Wood Company's
Refined Iron
Wellsville Polished Steel Sheets

New Microscope for Nature Study
and for use in the Examination of Ores, Metals, Woods, Fibre, etc.
Queen Acme No. 6 with 1 Ocular and giving power of about 100 diameters, 1 set of 12 prepared slides of insect parts and other interesting specimens, all in case, \$16.00.
Ask your nearest Optician for it.
QUEEN & CO., INC.
Optical and Scientific Instrument Works,
1010 Chestnut St., Phila., Pa.
Write for Circular. 59 Fifth Ave., New York.

Acetylene Gas Burners.
Schwarz Perfection Lava Burner.
Highest awards in all Acetylene Expositions. Made of one piece of lava. Are faultless and every one tested and guaranteed.
Sole Agents for the U. S. and Canada.
M. KIRCHBERGER & CO.
50 Warren Street, New York.

THE AUTO-CARBURETTOR
made upon a new principle furnishes a reliable explosive mixture. Easy ignition and greatest expansion. No pump required. Uses any grade of gasoline with no waste. Especially adapted to automobile and cycle motors. Our customers say it is the best Carburetor in the market. We make also the Regulator Valve for controlling the flow of gasoline or other fluids. Write us for prices and booklet on Carburetors. Gasoline and Steam Engines and Automobiles built to order and repaired.
The Avery & Jenness Co., 60 South Canal St., Chicago.

ARMSTRONG'S NO. 0 THREADING MACHINE
Can be attached to bench or post. Designed for threading the smaller sizes of pipe, iron or brass, also bolts. Has two speeds, one for pipe 1/4 to 1 inch, the other for pipe 1 1/4 to 2 inches, inclusive. Uses the regular Armstrong adjustable dies. Other attractive features. Send for particulars.
Wm. G. Armstrong Mfg. Co., 130 Centre Street, New York. Bridgeport, Conn.

INDUCTION COILS for experiments in X rays and other electrical work.
Catalogue Free.

E. S. RITCHIE & SONS, BROOKLINE, MASS.
MAXIMUM POWER—MINIMUM COST.
If you use a pump for beer, lard, acids, starch, petroleum, brewer's mash, tanners' liquor, cottonseed oil or fluids, hot or cold, thick or thin you want to get the **TABER ROTARY PUMP** which does the most work at the least expense. Simply constructed. Can be run at any desired speed. Perfectly durable. All parts are interchangeable. Needs no skilled workman. Defects guaranteed. Catalogue free.
TABER PUMP CO., 32 Wells St., Buffalo, N. Y., U. S. A.

FOR VEHICLE AND MARINE PURPOSES.
Nothing better or more economical than our four-cylinder motors. Possess every known point of excellence. Durable in every part. Detachable igniters, heavy bearings and shifting spark, water-jacketed head, runs any speed from 100 to 1500 per minute. 4 1/2 to 10 H. P. Fully guaranteed. Ground joints throughout.
Buffalo Gasoline Motor Co., Buffalo, N. Y., U. S. A.
Apply for Catalogue.

SENSITIVE LABORATORY BALANCE.
By N. Monroe Hopkins. This "built-up" laboratory balance will weigh up to one pound and will turn with a quarter of a postage stamp. The balance can be made by any amateur skilled in the use of tools, and it will work as well as a \$125 balance. The article is accompanied by detailed working drawings showing various stages of the work. This article is contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1158. Price 10 cents. For sale by MUNN & Co., 361 Broadway, New York City, or any bookseller or newsdealer.

A Marvelous Machine!
Watch the wonderful work done by our **Apex Nipple and Pipe Mill Machine**. Thread nipples of all sizes. So swiftd that it can be reversed and pipe cut off close to grippers. Vise can be opened or closed while machine is in motion. Send for Catalogue.
MFG. THE MERRILL STREET, Toledo, Ohio.



EASE OF REPAIR

You have probably seen the kind of tires that riders swear at.
G & J Tires are the kind they swear by—always faithful in service and easy to repair.
A puncture has no terrors for the G & J riders—no tools of any kind required.
Ask for G & J Tires and do not be put off with a substitute. Art catalogue free.

G & J TIRE COMPANY,
Indianapolis, Ind.

SATISFACTION GUARANTEED.

Acetylene Gas Generation PERFECTED.

The apparatus embodies entirely new principles. Safe, automatic, simple to install and operate. Next to daylight in cost and quality. Any capacity from table lamps to town plants. Also high grade "Criterion" stereopticons.

J. B. COLT CO.,
Dept. S, 21 Barclay St., New York.
Boston. Chicago. Philadelphia.

MILLS FOR ALL MATERIALS.

OUR BUSINESS IS TO MAKE MACHINERY FOR GRINDING GRAIN, CRUSHING ROCKS AND PULVERIZING ALL HARD SUBSTANCES. WE HANDLE ALL KINDS OF MATERIALS FROM COTTON SEED TO ROOTS AND HERBS. BY AN UNEXCELLED PROCESS IF YOU WANT ANY KIND OF A MILL OR GRINDING MACHINE, COME TO US AND YOU WILL GET THE BEST AND STILL SAVE MONEY.

DEAL WITH US ONCE AND YOU WON'T CHANGE.
ESTIMATES FREELY FURNISHED.
SPROUT, WALDRON & CO.
SEND FOR CATALOG NO. 4. MUNCY, PA.

OIL AND SMELTER!

The Union Consolidated Oil Co.
with over 17,000 acres of valuable proven oil lands, and a monthly production of 3,400 barrels.

Equivalent to Over 2% Monthly
on the entire amount invested in its stock; the

Standard Smelting & Refining Co.

with its plant of 250 tons capacity now under active construction in Yavapai County, Ariz., to be completed and in operation in August, promise larger dividends and immediate profits than any mining or industrial investment now before the public. We are Fiscal Agents for 8 mining companies, of which

4 Are Paying Regular Monthly Dividends.

The Union Consolidated Oil Company will begin dividends in May, and The Standard Smelting & Refining Company, as soon as its plant is in operation in August; the other two rapidly approaching a dividend-paying basis. A limited amount of the stock of the former Company is offered at 1 1/2 cents per share and of the latter Company at 40 cents per share, both full paid and non-assessable; or the two in combination at 55 Cents Per Share.

Prospectus of each Company, latest reports, subscription blanks and full particulars on application.

DOUGLAS, LACEY & CO.,
BANKERS AND BROKERS,
Members New York Consolidated Stock Exchange,
66 Broadway and 17 New St., New York.

BRANCHES:

Cleveland, "The Cuyahoga" Building.
Boston, "The International Trust Co." Building.
Philadelphia, "The Betz" Building.
Chicago, "The Fisher" Building.
St. Louis, "The Security" Building.
Hartford, Conn., "Hill's Bank" Bldg.
New Haven, Conn., "First Nat. Bank" Bldg.
Cincinnati, "The Union Trust" Building.
St. John, N. B., "The McLaughlin" Buildings.
Montreal, Can., "The Temple" Building.
London, Eng., "The Trafalgar" Buildings.

"HOT BATH IN ONE MINUTE"

FOR ONE CENT.

Moses, by the aid of a rod, struck a rock and got cold water. You by the aid of a Humphrey Crescent Heater strike a match and get hot water. They require no complicated piping, simply connect with water and gas in your bathroom. Guaranteed.


Write for Booklet.
HUMPHREY MFG. & PLATING CO., Kalamazoo, Mich.

"NEW GEM" SAFETY RAZOR

IMPOSSIBLE TO CUT THE FACE. BEST AND SIMPLEST SAFETY EVER DEvised. NO EXPERIENCE REQUIRED. WE GUARANTEE AND KEEP THEM SHARP FOR ONE YEAR. PRICE \$2.00 POSTPAID. SEND FOR ILLUSTRATED PRICE LIST.
THE GEM CUTLERY CO.,
37 READE ST. NEW YORK.

Feed water heater and purifier, E. R. Stillwell.....	672,497
Feed water purifier, N. L. Hayden.....	672,553
Feeder for steam boilers, automatic water, A. L. Hein.....	672,734
Fence machine, automatic, J. Harris.....	672,764
Fence post, Mullenix & Driver.....	672,825
Files, follower clamp for document, D. E. Hunter.....	672,530
Filter press, J. Critchlow.....	672,505
Filter press, R. C. Congdon.....	672,592
Filter, water, A. W. Bodell.....	672,846
Finger ring tray, W. Loeb.....	672,561
Firearm magazine closure, Kjellman & Andersson.....	672,783
Fire escape, J. M. Woodruff.....	672,544
Fire escape, J. Jennings.....	672,623
Flue cleaner, R. A. Rung.....	672,570
Flue cutter and roller, J. Mackenzie.....	672,448
Folding chair, legless, H. W. Potteiger.....	672,683
Folding stand, L. P. Halladay.....	672,705
Friction roller, J. P. McElroy.....	672,510
Fruit grading machine, S. McGarvin.....	672,453
Fruit juices, device for extracting, C. W. Taylor.....	672,721
Furnace, R. E. Davis.....	672,595
Furnace tapping device, electric, O. Frolich.....	672,601
Galvanic battery, C. B. Schoenmehl.....	672,715
Game apparatus, R. C. Brown.....	672,821
Game, bagatelle, H. W. Hoops, Jr.....	672,771
Game board, L. L. Lounsbury.....	672,839
Game piece, J. W. Gedney.....	672,478
Garment and hammock, combined, J. Conley.....	672,730
Garment fastener, W. G. & L. Pfeiffer.....	672,512
Garment hanger, F. P. Johnson.....	672,777
Garment union, J. Conley.....	672,720
Gas and coke, apparatus for the manufacture of illuminating, E. R. Besemfelder.....	672,694
Gas burner, C. F. Allen.....	672,748
Gas burner, Bennett & Jones.....	672,817
Gas burner, acetylene, C. T. Willson.....	672,502
Gas burner, incandescent, C. W. Taylor.....	672,503
Gas or gasoline engine, J. Doorenbos.....	672,615
Gate, See End gate.....	672,792
Gate, H. L. Mitchell.....	672,784
Gearings, compensating, Kramer & Blum.....	672,779
Gearing, variable speed, L. Jones, Jr.....	672,717
Glass articles, blowing necked, H. Semple.....	672,716
Glassware blowing machine, H. Semple.....	672,496
Glove fastener socket member, J. R. Smith.....	672,837
Grain distributor, R. Galloway.....	672,478
Grain drill, E. O. Edwards.....	672,478
Grain drill, Denyes & Schuch.....	672,669
Grate, A. C. Fletcher.....	672,675
Grinding harvester sections, mechanism for, J. H. Kennedy.....	672,557
Grinding machine, A. Johnston.....	672,690
Gun, machine, F. Alessi.....	672,701
Gutter hanger and screen retainer, M. J. Daniel.....	672,506
Hair crimper, E. R. Godward.....	672,816
Hair fastener, L. Bassett.....	672,552
Hammer, pneumatic, J. Dunlop.....	672,731
Hammer, shaft upsetting, J. P. Harrington.....	672,485
Hammock and accoutrements, combined, J. Conley.....	672,708
Hanger, See Garment hanger. Gutter hanger.....	672,709
Harrow, disk, J. Lindstrom.....	672,772
Hat fastener, M. B. Mosher.....	672,688
Hay elevator, W. McMenish.....	672,509
Hay fork, F. A. Howard.....	672,876
Heater, J. R. Vance.....	672,834
Heating apparatus, J. F. McElroy.....	672,521
Heating device, A. D. Campbell.....	672,438
Heel trimming machine work rest, E. E. Canedy.....	672,652
Hinge, spring, Cooper & Kirkpatrick.....	672,819
Hobby horse and tricycle, combined, F. E. Black.....	672,818
Hook and eye, W. Robinson.....	672,543
Hop drying apparatus, A. Blackie.....	672,760
Horse detach, W. S. Berry.....	672,480
Hose reel, R. D. Wirt.....	672,658
Hosiery supporter, S. Gardner.....	672,845
Hot air furnace, J. F. Hall.....	672,684
Hot air furnace, W. Wewers.....	672,481
Hot-air furnace, F. W. Beech.....	672,567
Hydrocarbon burner, C. A. Rosier.....	672,692
Incandescent mantle support, M. Herskovitz.....	672,711
Insulated railway rail joint, G. A. Weber.....	672,866
Ironing machine for collars and cuffs, smoothedge, G. E. Norris.....	672,710
Jars, etc., aerating cap for, A. R. Bailey.....	672,635
Kinetographic apparatus, W. H. Reid.....	672,879
Knob, door, G. E. Tyson.....	672,880
Knot tying implement, H. D. Coleman.....	672,597
Lamp, Toltz & Lipschutz.....	672,770
Lamp, ceiling, Toltz & Lipschutz.....	672,642
Lamp, electric arc, A. De Puydt.....	672,825
Lamp, electric arc, C. J. Holmok.....	672,861
Lamp, electric incandescent, Hollub & Mignall.....	672,489
Lamp, gas, J. Franklin.....	672,639
Lamp, street, W. H. Shlack.....	672,607
Lamp supporting device, electric, E. J. McAllister et al.....	672,790
Lamps, conductor and contact for electrical glow, J. A. Halford.....	672,647
Lamps, glow supporting plug for electric, Van Vleck & Stevens.....	672,742
Lantern igniter, F. Meyrose.....	672,490
Last for use in manufacture of rubber shoes, C. F. Parker.....	672,535
Lathe, turret, Potter & Johnson.....	672,751
Laundry bag, J. J. Tully.....	672,829
Legging, A. M. Lungard.....	672,755
Letter attaching device, E. Caesar.....	672,492
Lighting and heating apparatus, J. S. Goodwin.....	672,594
Lineman's climber, P. S. Dumbolten.....	672,801
Liquid gage, A. Pollatsek.....	672,847
Lock, P. V. Cornils.....	672,832
Loom, filling supplying mechanism, J. H. Northrop.....	672,518
Machinery, automatic stop for heavy, F. H. Brewster.....	672,841
Mail bag catching and delivering apparatus, automatic, C. E. Locke.....	672,695
Mail box, W. D. Wright.....	672,843
Mallet or hammer, electric, C. D. Olsen.....	672,583
Malt kiln floor section, R. Bohnen.....	672,456
Maltster system, gravity pneumatic, P. Renner.....	672,545
Mangle, hand, W. H. Anderson.....	672,591
Match box, Paul & Hilbig.....	672,534
Match safe, T. A. Bell.....	672,782
Matches, machine for unloading, C. F. Christ.....	672,672
Matrices and stereotypes of celluloid, producing, Lichtenberg-Madsen.....	672,622
Measuring cabinet, J. M. Kinard.....	672,650
Medicated salt rock, C. O. Green et al.....	672,542
Micrometer gage, H. Isherwood.....	672,699
Mill, See Rolling mill.....	672,458
Miner's squib, E. Reese.....	672,444
Molding machine, S. H. Stupakoff.....	672,465
Mop wringer, Cody & Houwers.....	672,785
Motor, W. E. Rice.....	672,743
Musical instrument pad holder, L. T. Halle.....	672,668
Nail or spike, G. T. Walker.....	672,554
Nut lock, T. W. Hine.....	672,702
Nut lock, P. Labr.....	672,628
Oils, oxidizing, A. S. Ramage.....	672,541
Package covers, fastening device for fabric, D. R. C. Devine.....	672,454
Pan scraping and cleaning machine, R. Henkel.....	672,487
Paper feeding machine sheet caliper device, T. C. Dexter.....	672,681
Paper folding machines, automatic point for, C. Sturtevant.....	672,746
Paraneoproteids, manufacture of transparent products from impure, A. Spitzler.....	672,441
Pasteurizing machine, N. D. Nelson.....	672,723
Pattern plate for folding and marking garment sections, P. J. Menahan.....	672,605
Pavement, driveway, W. A. Mundy.....	672,873
Pen extractor, Van Wyck & Phillips.....	
Pencil sharpener and eraser, combined, A. G. De Waldo.....	
Pencils to memorandum or other books, means for holding, M. Vernon.....	
Photographic negative washing apparatus, Orr & Smith.....	
Pintle forming die, R. F. Semple.....	

(Continued on page 286)



The "Khotal" Blue Flame Oil Stove

(FOR HOME OR CAMP OR YACHT)

generates gas from common kerosene. It will boil a quart of water in two minutes and cook a dinner quickly. It can be regulated to any desired degree of heat. It has no wick and no asbestos substitute. It is strong, durable and ornamental, being made of brass of superior finish and excellent workmanship. A child can operate it.

The "Khotal" costs little to buy and little to run. The combustion is perfect; no smoke, no smell, no soot deposit on pots and pans.

Picture shows smallest size, 8 ins. high, weight 5 1/2 lbs. Price \$3.75. Made in sizes large enough to cook a course dinner.

THE HYDROCARBON BURNER CO., 197 Fulton St., New York
Boston, Mass.: Globe Gas Light Co., 77-79 Union St.

Write for Free Illustrated Book G.

A PLEASURE LAUNCH

Must have speed, combined with safe and reliable power; she must be built upon lines of grace and beauty. The "Recreation" covers these requirements. In its use you are tranquil in mind, body and estate, no fixing and figuring upon "her going." Minimum weight, maximum power, economy of maintenance. Throttle speed regulator. Write for circular "S."

WESTERN GAS ENGINE CO., - - MISHAWAKA, IND.

Our Specialty:
Knock-Down
Boats of any description.

AMERICAN BOAT & MACHINE CO.
ROW, SAIL AND PLEASURE BOATS,
Marine Station. ST. LOUIS, MO.

OUR MARINE MOTORS
ARE GUARANTEED TO
GIVE SATISFACTION.
Durable in Construction and
Easy and Safe in Operation.
Send for Catalogue and
investigate our claims.
TRUSCOTT BOAT MFG. CO.,
St. Joseph, Mich., U. S. A.

PROSPECTIVE BOAT BUYERS.

By constructing your boat from a set of my Boat Building Materials more than one-half the boat factory's price can be realized. Also economize freight 500 percent. Launches, Sail and Row Boats, Gasoline Engines. Catalog free.
FRED MEDART, 3545 DeKalb St., St. Louis, Mo.

HOLD ON THERE!

Send 3c. for catalog of
Monarch Marine
Gasoline Engines
1/2 to 45 H. P. \$200 up.
Grand Rapids Gas
Engine & Yacht Co.,
Grand Rapids, Mich.

GERE GASOLINE ENGINES

SIMPLEST BOAT ENGINES MADE
CABIN AND OPEN BOATS
ENGINE CASTINGS, BOAT FRAMES
GEORGE YACHT LAUNCHING CO.,
NEW CAT FOR 4 STAMPS
GRAND RAPIDS, MICHIGAN.

Savings Banks 3% vs. Industry 12%

IF YOU Have some money in a savings bank or have investments that are paying you but three or four per cent., **WRITE TO US** and we will show you our plan for the investment of your money where it will probably net you 12 per cent. per annum.

The United States Steel Company

Has been established for two years, and we have one plant which alone cost us \$250,000, but it is too small to fill the orders for JUPITER STEEL CASTINGS.

The capital stock of The United States Steel Company is three million dollars, divided into six hundred thousand shares, with a par value of \$5.00 each. Every share is full paid and non-assessable. Three hundred and forty thousand shares of this stock have been issued, and for eighteen months a dividend of 12 per cent per annum has been paid on the outstanding stock.

The United States Steel Company has the sole right to manufacture JUPITER STEEL CASTINGS, which are castings of the quality of forgings, and the NEAL DUPLEX BRAKE, which is now in use on the system of the Boston Elevated Railroad and other roads. See description, April 6, of this paper.

To provide further capital for the enlargement of their plant, so that they can supply the demand for Jupiter Steel Castings and to build the Neal Duplex Brakes, the Board of Directors have authorized the sale of ten thousand shares of the treasury stock at par (\$5.00) per share.

We will be pleased to send to those who are interested in an investment a full prospectus of this company, together with a record of what has been accomplished in the past two years.

THE UNITED STATES STEEL COMPANY

143 OLIVER STREET, BOSTON, MASS.

The "Wolverine" Three Cylinder Gasoline Marine Engine.

The only reversing and self-starting gasoline engine on the market. Lightest engine for the power built. Practically no vibration. Absolutely safe. Single, double and triple marine and stationary motors from 1/2 to 30 H. P.

WOLVERINE MOTOR WORKS,
Grand Rapids, Mich.

THE STEAM TURBINE; THE STEAM Engine of Maximum Simplicity and of Highest Thermal Efficiency. By Prof. R. H. Thurston. A valuable series of articles having cuts of some of the more efficient engines of this type—the Parsons, DeLaval, Dow, etc.; with exhaustive tables giving the result of tests and much general data on the subject. Contained in SUPPLEMENT Nos. 1306, 1307 and 1308. Price 10 cents each. For sale by Munn & Co. and all newsdealers.

GREAT POWER—SMALL COST.

The maximum of strength, durability and safety, with the minimum of cost that describes our **Holding Engines** for operation on Gasoline, Distillate or Crude Oil. Every part of the engine is interchangeable. Soon saves its cost in fuel alone. Both friction and geared hoist, 6 to 150 h.p. For quarries, mines, and docks. **Weber Gas & Gasoline Engine Co.,** P. O. Box 1114 a, Kansas City, Mo.

A. LESCHEN & SONS ROPE CO.

MANUFACTURERS OF
LESCHEN CO.'S PATENT AERIAL WIRE ROPE TRAMWAY.

The only satisfactory Tramway on the market.
ESTIMATES ON APPLICATION.
MAIN OFFICE:
920-922 North First Street, ST. LOUIS, MO.



HERCULES WIRE ROPE
And all kinds of WIRE ROPE, Manila, Sisal, Blocks, etc.
Branch Offices: 52 Centre St., New York.
47-49 So. Canal St., Chicago, Ill.

PERFORATED METAL
OF EVERY DESCRIPTION
AND FOR ALL USES.
THE HARRINGTON & KING PERFORATING CO., 225 N. UNION ST., CHICAGO, ILL., U.S.A.



**Powerful, Responsive,
Durable and Efficient.**

**"The Reeves"
Variable Speed
Countershaft**

for securing any speed without change of belt or loss of time. Especially adapted for all kinds of Iron-working Machinery, Iron Lathes, Planers, Boring Mills, Shapers, etc. Cement Machinery, Experimental Machinery in fact all kinds of machinery requiring a change of speed. With it a large increase and a better grade of work can be produced.

Send for handsomely illustrated catalogue "S. A." free.

**REEVES PULLEY CO.
COLUMBUS, IND., U. S. A.**

HIGHEST EFFICIENCY
attained in the

**STOVER
GASOLINE
ENGINE**

The best is always cheapest. Write for prices.

STOVER ENGINE WORKS, FREEPORT, ILL.

**THE MIETZ & WEISS KEROSENE
and GAS Engine**

burns KEROSENE cheaper and safer than gasoline. Automatic, simple, reliable. No electric battery or flame used. Perfect regulation. Belted or directly coupled to dynamo for electric lighting, charging storage batteries and all power purposes.

Send for Catalogue.

**A. MIETZ,
108-110 N. 1st St., NEW YORK.
Mark & Co., London, Hamburg, Paris**

The AUTOSPARKER
The completion of the Gas Engine.

Throw away your batteries and use them no more. The Autosparker saves its cost many times over during the life of your engine. Address

**MOTINGER DEVICE
MFG CO.,
Pendleton, Ind., U. S. A.
or any gas engine or
motor carriage manufacturer.**

**BACKUS GAS AND
GASOLINE ENGINE**

Simple. Economical. Durable.
Suitable for all kinds of work.

Backus Water Motor, cheapest power known.
Write for circular and prices.

BACKUS WATER MOTOR CO., Newark, N. J., U. S. A.

**SETS OF CASTINGS OF
MODEL ENGINES**
SEND 10¢ FOR 126 PAGE
ILL. CATALOGUE.

**ALSO TOOLS
GEAR WHEELS & PARTS OF MODELS**

GOODNOW & NIGHTMAN

GASOLINE CASTINGS

MOTOR

For MARINE, VEHICLE and
BICYCLE MOTORS,
with Working Drawings.

LOWELL MODEL CO., 22 Wiggin St., Lowell, Mass.

**GAS and GASOLINE
ENGINES**

1-4 and 1 horse power
MARINE and STATIONARY.

Built in accordance with the latest practice in Gas Engine design. Also complete set of castings. Write for particulars.

**CLIFTON MOTOR WORKS,
233 E. Clifton Ave., Cincinnati, Ohio.**

Motor Generators For Charging Storage Batteries, etc.

If your local electric supply current is not the correct voltage or character for charging your batteries or operating any particular style of machine you may have, we can provide you with a motor generator that will economically transform the available current to any desired voltage or character. Advise us what you wish to do and we will give you particulars and quote you on a machine best adapted for your purpose.

The Holtz-Cabot Electric Co., Boston, Brookline, Mass.

**ACETYLENE GAS AND CARBIDE OF
Calcium.**—All about the new illuminant, its qualities, chemistry, pressure of liquefaction, its probable future, experiments performed with it. A most valuable series of articles, giving in complete form the particulars of this subject. Details of furnaces for making the carbide, gas generators, gasometers, burners, etc. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 998, 1001, 1002, 1012, 1014, 1015, 1016, 1022, 1035, 1038, 1057, 1064, 1071, 1072, 1082, 1083, 1084, 1085, 1086, 1104, 1124, 1132, 1149 and 1150. Price 10 cents each, by mail, from this office, and all newsdealers.

**HOT BLAST
WATER JACKET
FURNACES
FOR
COPPER ORES.**

**MATTE from SULPHIDES
AT ONE OPERATION.**

**UNION IRON WORKS,
San Francisco, Cal., U. S. A.**

Send for Catalogue.

Pintle retainer, Norblad & Markham.....	672,490
Pipe coupling, W. F. Drew.....	672,598
Pipe wrench, G. E. Stansbury.....	672,461
Planimeter, E. J. Willis.....	672,581
Planter check row lever, corn, J. Kaylor.....	672,559
Pliers, E. N. Sperry et al.....	672,654
Pliers, Hobbs & Sperry.....	672,673
Flow, E. Press.....	672,649
Flow, combined turning and leveling, F. Collins.....	672,752
Poison, safeguard for bottles containing, J. W. Ogden.....	672,840
Pole or shaft coupling, E. Childs.....	672,871
Polishing machine, E. D. Woods.....	672,661
Portable elevator, W. G. Adams.....	762,471
Pulley, clutch, C. Newson.....	672,800
Pump, F. C. Billings.....	672,435
Pump, C. L. Parker.....	672,537
Pump valve, Hack & Weir.....	672,551
Pump, wind and water power, E. Graham.....	672,762
Punching machine strap, R. G. Armstrong.....	672,585
Punching metal strips, machine for, J. S. Stokes.....	672,685
Quitting frame, S. S. Russell.....	672,869
Rail joint, J. Booth.....	672,870
Railway appliances, actuating mechanism for, automatic, S. W. Hoff.....	672,445
Railway brake, M. Vidie.....	672,632
Railway, rails for splicing, forming ends of, J. S. Holme.....	672,769
Railway signal, J. D. Price.....	672,626
Railway signal system, Hoffman & Powers.....	672,830
Railway tie plate, J. W. Stephenson.....	672,719
Rasp, K. Kellermann.....	672,780
Recorder, H. L. Arnold.....	672,586
Reflector, street lamp, R. Thayer.....	672,865
Refrigerator and water cooler, combined, J. E. Bimm.....	672,437
Register and ventilator, H. S. Hart.....	672,765
Reservoir or basin, settling, W. P. Mason.....	672,486
Rock breaking, T. A. Edison.....	672,616
Rock breaking apparatus, T. A. Edison.....	672,617
Roller. See Friction roller.	
Rolling machine, G. A. Gulowsen.....	672,525
Rolling mill adjusting mechanism, R. Wayland-Smith.....	672,466
Rolling mill, axle, J. Schmeidler.....	672,516
Rolling sheet metal, C. B. Cushman.....	672,687
Rotary cutter, Anderson & Hardart.....	672,519
Rotary engine, W. H. Crowe.....	672,700
Rotary motor, E. M. Ball.....	672,874
Roving can, cordage can, or basket, G. S. Perkins.....	672,804
Rubber boot or shoe sole, A. F. Vogt.....	672,724
Ruling spindle, adjustable ring, D. E. Hunter.....	672,528
Ruling spindles, machine for spacing adjacent, justable, D. E. Hunter.....	672,527
Sash, combination sliding and pivoted window, A. J. Skillman.....	672,539
Sash, ventilating, P. & W. Deissler.....	672,754
Saw, J. Bonis.....	672,587
Saw attachment, F. O. Helsten.....	672,767
Saw machine, back, L. H. Olmsted.....	672,802
Saw set, J. Wesley.....	672,517
Saw sharpening implement, G. Y. Anderson.....	672,691
Sawing machine, T. Thill.....	672,498
Scaffold, window, J. T. Saunders.....	672,515
Scraper, wheeled, T. R. McKnight.....	672,798
Screen. See Shaker screen.	
Seal lock, L. P. Jewett.....	672,736
Seal lock, G. B. Edgar.....	672,853
Sealing machine, bottle, H. T. Gay.....	672,671
Seeders, harrows, etc., tooth for, R. E. Schley.....	672,572
Seine pursing apparatus, J. Savoy.....	672,572
Separator, G. C. Hunter.....	672,531
Sewage, plant for disposal of, J. Danner.....	672,614
Sewer cleaning device, M. T. Connolly.....	672,593
Sewing machine needle, W. H. McLeod.....	672,682
Sewing machine, overswinging, J. Weir.....	672,467
Sewing machines, guide operating mechanism for sole, F. E. Bertrand.....	672,611
Shade and curtain supporter, combination, M. E. Kisor.....	672,677
Shaft and journal therefor, F. M. Kennedy.....	672,706
Shaft coupling, compression, S. Moltrup.....	672,794
Shifting, machine for turning, B. Dreyer.....	672,872
Shaker screen, F. W. Bond.....	672,696
Shears, H. Crann.....	672,547
Sheet metal strips into tubular form, machine for bending, L. E. Whitehouse.....	672,680
Sheets, signatures, etc., machine for feeding or gathering, E. F. Goodman.....	672,761
Shell for high explosives, L. Gathmann.....	672,827
Shell for shotguns, rifled bullet, P. O. Elterich.....	672,824
Shells, safety fuse for high explosive, L. & E. Gathmann.....	672,826
Shoe, L. Roadhouse.....	672,569
Shoe, H. Ries.....	672,651
Show case, F. J. & J. A. Bank.....	672,693
Sidewalk, W. J. Caldwell.....	672,822
Sink, A. Plavin.....	672,805
Skate, O. W. Everett.....	672,756
Soldering iron, Arnman & Loring.....	672,433
Spark arrester, L. L. Crump.....	672,753
Spinning machine, A. Haenichen.....	672,443
Spoke fastening, E. T. Wheeler.....	672,747
Spraying apparatus or device, M. B. Brooks.....	672,820
Square, M. Nicholls.....	672,455
Stacker, pneumatic straw, G. F. Conner.....	672,732
Stair lift, J. M. Dodge.....	672,823
Stay bolt, flexible, J. B. Barnes.....	672,852
Steam boiler, J. J. Tonkin.....	672,464
Steam boiler, reversible, T. W. Moran.....	672,795
Stereoscope attachment, R. Y. Young.....	672,609
Stereotyping plate, F. A. Ringler.....	672,859
Stove, gas, C. M. Stroud.....	672,844
Stove, hot air heating, J. F. Freeland.....	672,836
Stovepipe joint, D. S. Durall.....	672,548
Surface gage, S. H. Bellows.....	672,634
Switch. See Electric switch. Electrical switch Table or stand, H. T. Sidway.....	672,573
Tank heater, C. T. McCarroll.....	672,565
Teaching device, music, C. Kitching.....	672,678
Telautograph, G. S. Tiffany.....	672,629
Telephone, desk, A. K. Andriano.....	672,662
Telephone metering system, D. M. Bliss.....	672,546
Telephone transmitter, C. C. Hughes.....	672,621
Thermometer, R. Granville.....	672,437
Threshing machine, C. H. Falk.....	672,533
Tire and rim, wheel, H. D. Lefebvre.....	672,657
Tobacco bag attachment, J. A. Vautrot.....	672,657
Tobacco bag closure and feeder, C. R. Siegel.....	672,860
Tobacco treating apparatus, J. K. Proctor.....	672,806
Towel rack, L. P. Greenen.....	672,479
Toy, mechanical, B. F. Schwler.....	672,538
Trolley, mechanical, Mackin & Zweigart.....	672,707
Trolley, Hoffman & Powers.....	672,835
Trolley electric railway, C. H. Meyers.....	672,741
Trolley for electric railway cars, A. Schneider.....	672,653
Tug, hame, C. R. Rapson.....	672,457
Tug locking strap, J. B. May.....	672,450
Turbine, fluid pressure, F. Hodgkinson.....	672,838
Turning machine, G. N. Toms.....	672,463
Typewriter, Fox & Barrett.....	672,823
Typewriter, R. Granville.....	672,849
Typewriting machine, N. R. Marshman.....	672,680
Valve and closet cistern, antifreezing, G. W. Wilkes.....	672,469
Valve, reducing, S. W. Lewis.....	672,787
Valve, rotary steam, J. M. Redlingshafer.....	672,627
Valves, mechanism for controlling throttle and cylinder, F. C. Billings.....	672,436
Vapor burner, A. Rotzian.....	672,666
Vehicle draft attachment, G. Swinehart.....	672,575
Vehicle steering device, motor, S. E. F. man.....	672,670
Vehicle steering mechanism, J. P. Horton.....	672,620
Vehicle steering mechanism controller, A. F. Madden.....	672,644
Vehicles moving on the rails, means for supplying power from stationary rails to, R. C. Sayer.....	672,459
Vessels, device for closing discharge orifices of, H. Hirt.....	672,641
Wagon, dumping, W. J. Hall.....	672,704
Watch barrel, J. Thalhofer.....	672,655
Watch, winding and setting, A. Bannatyne.....	672,728
Water cooling tank, J. Wolfensperger.....	672,504
Water marks, production of, Affeltranger & Zweifel.....	672,582
Weather strip and threshold, combined, A. Frysle.....	672,759
Web feeding device, J. H. Sturges.....	672,745
Weeds, etc., machine for the destruction of, C. Panten.....	672,709
Welding aluminium and aluminium alloys, M. Schmidt.....	672,744

(Continued on page 287)

GENTLEMEN:—The GOODFORM Trousers
Hanger is made of fine, specially rolled spring steel, heavily nickel-plated on copper. The parts in contact with the fabric are wide and the edges rounded. It operates automatically. "You press the button," and the keeper does the rest. Sample by mail, 35c.; 3 for \$1.00; 6 and a closet loop, \$2.00. All express prepaid. This is what you want if you want the best.

Sold by Hardware and Furnishing stores, or prepaid for the price. Remit to the maker.

CHICAGO FORM CO., Dept. 76, 124 La Salle St., CHICAGO

**PATTON'S
Sun
Proof Paints**

are guaranteed to protect the house five years. Send for free book about paint. Inducements to dealers.

**PATTON PAINT CO.,
227 Lake St., Milwaukee, Wis.**

IMPROVED GASOLINE BURNER

Gas is admitted through circular slots instead of perforations. It is fitted with pilot light. Can be left burning any length of time. Carriage is always ready to start. This burner is a quick steamer, gives a blue flame, and will not light or blow back. Is fitted with automatic fire regulator which shuts gas off from main burner at any desired pressure.

FRANK MILNE, Everett, Mass.

THE JOHNSON ROTARY PUMP.

Simple of construction, positive in action, easy and quiet in operation. Especially adapted to pumping soap, oil, sugar, lard, glue, acids, starch, ketchup, varnish, and water, malt, etc. Large sizes for irrigation. Made as a belt or steam pump, or combination, or operated by electric motor or gasoline engine. Manufactured by

**DAVIS-JOHNSON CO., Station V, CHICAGO, ILL.
James H. Robley, Agent, 95 Liberty St., N. Y. City.**

DRIVING A PLEASURE
when holding your horse with an IMPERIAL BIT, giving 100 per cent more leverage than any other. Any lady can control the most vicious horse. Positive cure for tongue-lolling. Will prevent side pulling and driving on one line. Sent to any address postpaid, upon receipt of price. In X.C. plate or imitation rubber, \$1. In fine nickel plate, \$2.

Imperial Bit and Snap Co., 14th Street, Racine, Wis.

SHORTHAND BY MAIL. Pioneer home course Catalogue and First Lesson Free.

Potts Shorthand College, Box 33, Williamsport, Pa.

WILL SHIP C. O. D. FOR \$25.00

WITH PRIVILEGE OF EXAMINATION.
FREIGHT PREPAID TO YOUR STATION.

"THE WILLARD STEEL RANGE"

Has 6-8 in. lids, oven 17x21x12, 15-gallon reservoir and warming closet, lined throughout with asbestos, burns wood or coal. This special inducement is offered for a limited time only. Mention this paper.

WM. G. WILLARD, Manufacturer, 619 and 621 N. 4th St., St. Louis, Mo.

SAVE MONEY BY USING THE

COMMERCIAL MUTOSCOPE.

Takes the place of expensive demonstrations. A moving picture showing your device in action. In a small, compact traveling case. Infinitely superior to models. Send for illustrated pamphlet and prices.

AMERICAN MUTOSCOPE & BIOGRAPH CO., 841 Broadway, New York.

The Deadly Faucet!
From it comes the germ-laden water carrying with it all the elements of disease, but if you use

The Berkefeld Filter
the water will be thoroughly purified in passing through the cylinders of Infusorial Earth which retains every atom of solid matter. Easy to clean. Yields a gallon of pure water in 4 minutes.

BERKEFELD FILTER CO., 2 Cedar St., New York.

**TUBULAR
DRIVING LAMP.**

IT is the only perfect one. IT will not blow or jar out. IT gives a clear, white light. IT is like an engine head-light. IT throws the light straight ahead from 200 to 300 ft. IT burns kerosene. Send for book (free).

R. E. DIETZ CO., 60 Lighthouse St., New York.
Mention this paper and get special discount.

ESTABLISHED 1840.

MORAN FLEXIBLE JOINT
for Steam, Air or Liquids.
Made in all sizes to stand any desired pressure.

**Moran Flexible Steam Joint Co., Inc'd.
149 East 3d St., Louisville, Ky.**

ROTARY ENGINES.—ARTICLES ON
this type of engine, giving many details and illustrations, are contained in SUPPLEMENT Nos. 1138, 1156, 1193 and 1309. Price 10 cents each. For sale by Munn & Co. and all newsdealers.

**ELEVATING - CONVEYING
POWER TRANSMISSION MACH'Y
COAL WASHING MACHINERY**

U. S. A.
The Jeffrey
Columbus, O.

**FOR
GUNSMITHS, TOOL
MAKERS, EXPERI-
MENTAL & REPAIR
WORK, ETC.**

From 9-in. to 13-in. swing. Arranged for Steam or Foot Power, Velocipede or Stand-up Treadle.

W. F. & John Barnes Co., 1999 Ruby St., Rockford, Ill.

THE ORIGINAL AND GENUINE ::

The Windsor Gowns
Save Lasting Bills

Rubber Goods. Perfectly imitate linen. Are durable and keep white. They go to all parts of the Globe. Write for Catalogue. We want Agents everywhere. M'd only by

**Windsor Collar & Cuff Co.,
Windsor, Conn.**

ROTARY PUMPS AND ENGINES.
Their Origin and Development.—An important series of papers giving a historical resume of the rotary pump and engine from 1588 and illustrated with clear drawings showing the construction of various forms of pumps and engines. 38 illustrations. Contained in SUPPLEMENTS 1109, 1110, 1111. Price 10 cents each. For sale by Munn & Co. and all newsdealers.

**DICKERMAN'S
DURABLE DESKS**

Don't buy until you get our catalogue—100 pages of money saving values.

AMERICAN STORE STOOL CO., 33 Howard St., New York

ASK FOR and INSIST on getting the quick open and quick shut 20th CENTURY UMBRELLA.
It will save your gloves, fingers and temper.

50th Century Umbrella Runner.

This is what A. H. BAMBERGER, 381 Broadway, New York, does the trick.

Pat. Jan. 9, 1900.

EMPIRE GEARLESS TRANSMISSIONS
FOR
AUTOMOBILES & TRICYCLES

**EMPIRE MOTOR WKS, 888 WASHINGTON ST.,
BUFFALO N. Y.**

**Building Edition
Scientific American**

MONTHLY, \$2.50 PER ANNUM.
SINGLE NUMBERS, 25 CENTS.

The BUILDING EDITION for 1901 is the handsomest magazine in the United States. It has many new and important features. Send 25 cents for the March number, and see the new departments. The illustrations and cover are more attractive than ever. Send for "Are You About to Build?" and be convinced.

NEW DEPARTMENTS.

Monthly Comment.
Interviews with Architects.
New Books.
New Building Patents.
Notes and Queries.
Digest of Current Articles.

MUNN & CO.,
Publishers, 361 Broadway, New York.

Coal Mining Machines
ELECTRIC MINE LOCOMOTIVES
POWER COAL DRILLS
COAL HANDLING MACHINERY

**UPRIGHT
DRILLS**

Complete line, ranging from Light Friction Disk Drill to 42" Back Geared Self-Feed. Latest improvements. Up-to-date in every respect.

Send for Catalogue.
Established 1872.

W. F. & John Barnes Co., 1999 Ruby St., Rockford, Ill.

The Search for Work

The man who can do something better than anyone else doesn't search for work. Employers search for him. We teach the theory of engineering and the trades to men already at work. Thousands of our students have secured a

Salary-Raising Education

in Mechanical, Electrical, Steam, Civil or Mining Engineering, Chemistry, Architecture, Plumbing, English Branches. When writing state subject in which interested.

International Correspondence Schools, Box 942, Scranton, Pa.



ELECTRICAL ENGINEERING TAUGHT BY MAIL.

Write for our Free Illustrated Book. "CAN I BECOME AN ELECTRICAL ENGINEER?"

We teach Electrical Engineering, Electric Lighting, Electric Railways, Mechanical Engineering, Steam Engineering, Mechanical Drawing, and other branches by mail. Institute Indorsed by Thos. A. Edison and others. **ELECTRICAL ENGINEER INSTITUTE,** Dept. A, 240-242 W. 28d St., New York.



LEARN TO WRITE ADVERTISEMENTS

Employed Graduates are making good salaries. More than 10 years' experience. **TAUGHT THOROUGHLY BY MAIL.** Ad. Writing is not genius but an easily acquired business. Answer this now. **Page-Davis School of Advertising,** Suite 20 167 Adams St., Chicago.

THE NEW BRISTOL COUNTER



Registers an accurate account of work done on printing presses, grain tallies, weighing, measuring and other automatic machines. Counts up to 1,000,000 and repeats automatically. Simple, accurate, durable. Special counters to order. **Send for circular.** **C. J. ROOT, Bristol, Conn., U. S. A.**

Perfection Air Mattresses

FOR - CAMP - YACHT - HOME - HOSPITAL. NON-ABSORBENT, HYGIENIC, ODDNESS. When deflated can be rolled into small package for storage or transportation. **Send for Illustrated Catalogue with Prices.** **Mechanical Fabric Co., Providence, R. I.**

Braddock Hydraulic and Steam Packing Co.
Braddock, Pa., U. S. A.
John C. F. Jones, Proprietor,
MANUFACTURER OF
Hydraulic and Steam Packing,
Including The "James" Hydraulic and Steam Hammer Packing and John C. F. Jones' Patent "Unique" Packing. Universally used by the most prominent Steel Plants in the United States. **Sample for Export furnished on application.**

10 DAYS' TRIAL
to responsible parties.
DAUS' TIP TOP
DUPLICATOR prints 100 copies in black from one pen written original and 50 copies from typewriter. It takes an expert to tell the duplicates from the original. **FELIX DAUS DUPLICATOR CO., 5 Hanover St., New York**

Telephones,
for Interior, Short Line, Intercommunicating and Hotel Work. Write us for prices, catalogue, etc., with testimonials and references. Estimates cheerfully furnished. Agents wanted.
THE SIMPLEX INTERIOR TELEPHONE CO.,
431 Main St., Cincinnati, Ohio.

ACETYLENE APPARATUS
Acetylene number of the SCIENTIFIC AMERICAN SUPPLEMENT, describing, with full illustrations, the most recent, simple or home made and commercial apparatus for generating acetylene on the large and small scale. The gas is made for and used by the microscopist and student; its use in the magic lantern. (The new French table lamp making its own acetylene.) Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1057. Price 10 cents prepaid by mail. For other numerous valuable articles on this subject we refer you to page 21 of our new 1897 Supplement Catalogue, sent free to any address. **MUNN & CO., 361 Broadway New York.**

MANDERY FENDERS
for Automobiles.
Saves Washing Wagons.
Write for particulars.
Rochester Automobile Co.,
Joseph J. Mandery, Prop.,
150 to 170 South Ave.,
Rochester, N. Y.

DIAMONDS & SAPPHIRES
for all mechanical purposes.
MENDES CUTTING FACTORIES,
12-16 John St., New York.

ARTESIAN
Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 3000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1200 feet. Write us stating exactly what is required and send for illustrated catalogue. Address **PIERCE WELL ENGINEERING AND SUPPLY CO., 130 LIBERTY STREET, NEW YORK, U. S. A.**

Well casing, F. W. Hunick.....	672,556
Well drilling attachment, E. D. Wolbert.....	672,470
Well machine, W. H. Cater.....	672,613
Wells, expensible, packing attachment for	
artesian, F. Cavallaro.....	672,475
Wheat, separating garlic from, J. K.	
Scheiner.....	672,833
Wheel molding apparatus, J. G. Johnston.....	672,778
Whiffletree, J. W. Hunter.....	672,856
Whist board, duplicate, F. H. Lewis.....	672,679
Wire drawing machine, J. H. O'Donnell.....	672,688
Wire systems, automatic booster in connection with multiple, J. S. Highfield.....	672,640
Wireworking tool, C. W. Carter.....	672,474
Wrench, J. H. Kaley.....	672,532
Wrench, Mahana & Pompe.....	672,737
Yoke link, neck, R. H. Higgins.....	672,482
Zinc bearing ores for obtaining zinc, etc., treating, S. O. Cowper-Coles.....	672,637

DESIGNS.

Advertising badge, M. J. & F. M. Owens.....	34,390
Badge, N. Stadler.....	34,391
Badge, etc., C. F. Burkhardt.....	34,392
Bath robe sleeve portion, M. M. Hovey.....	34,423
Belt, I. Isenstein.....	34,422
Bottle stopper, T. N. Jayne.....	34,431
Churn dasher, Davis & Duncan.....	34,398
Clip, L. C. Schomann.....	34,421
Cooking utensil, A. M. Dittler.....	34,405
Display and sale cabinet, A. F. Bell.....	34,404
Display fixture for stores, H. G. Roth.....	34,428
Fabric, D. J. Seaman.....	34,426
Fabric, woven, W. T. Smith.....	34,429
Fires, frame for gas, J. Stoertzenbach.....	34,420
Floor cloth, A. L. Bower.....	34,424
Floor cloth, C. M. Post.....	34,425
Hat pins, etc. spring support for ornaments of, A. A. McRae.....	34,396
Knife blade, child's, M. A. Herr.....	34,401
Meat tenderer frame, J. F. Filbrun.....	34,407
Package carrier, C. W. Smith.....	34,406
Picture frame, G. A. Wieser.....	34,402
Pin, etc., W. A. Spier.....	34,393
Range end, F. H. Buzzacott.....	34,412
Range fire chamber plate, F. H. Buzzacott.....	34,417
Range fire door, F. H. Buzzacott.....	34,413
Range grate, F. H. Buzzacott.....	34,415
Range oven door, F. H. Buzzacott.....	34,416
Range oven door, W. S. Essick.....	34,418
Range top truss, F. H. Buzzacott.....	34,414
Ring, C. P. Goldsmith.....	34,394
Ring, W. F. Juergens.....	34,395
Spoon, T. Calhoun.....	34,399
Spoons, etc., handle for, Osborne.....	34,400
Stock implement, cutting block head and handle stub, S. J. Brighton.....	34,409
Stock implement cutting head and handle stub, S. J. Brighton.....	34,410
Stove, P. G. Van Wie.....	34,419
Track side frame, W. S. Adams.....	34,411
Typewriting machine ribbon spool, J. A. Bedworth.....	34,403

TRADE MARKS

Boots and shoes, B. Rosenberg & Sons.....	36,285
Electrical appliances, devices, and machines, Franklin Electric Manufacturing Company.....	36,305 to 36,307
Films, certain named, B. Day.....	36,282
Flour, J. E. M. Milling Company.....	36,292, 36,293
Flour, wheat, Bennett Milling Company.....	36,291
Forks, farm and garden, Withington & Cooley Manufacturing Company.....	36,308
Herbs, liquid compound of, J. W. Cummins.....	36,303
Leather articles, cement, and dressing, certain named, National Leather Belting Company.....	36,286
Mailing lists, special trade and professional, E. J. Williams.....	36,283
Medical compounds, certain named, Evans & Shepard.....	36,290
Medicine, blood, B. S. Slocum.....	36,298
Medicine, certain named, G. Bohannan.....	36,301
Medicine, lung, Lung Germine Company.....	36,297
Medicines, certain named, McKesson & Robbins.....	36,300
Medicines, certain named, A. A. Klein-schmidt.....	36,302
Milk, condensed, St. Louis Condensed Milk Company.....	36,294
Mowers, lawn, Philadelphia Lawn Mower Company.....	36,309
Overcoats or jackets, men's or boys', Spitz, Landauer & Co.....	36,284
Packings, leather and rubber, Strong Machinery and Supply Company.....	36,287
Perfumeries and cosmetics, J. L. Leichter.....	36,295
Popcorn, L. A. Archer.....	36,289
Salve, A. Darce.....	36,304
Soda and baking powder, baking, Church & Dwight Co.....	36,290
Tablets, headache, C. A. Weida.....	36,296
Whisky, Nicholas Burke Company.....	36,288

LABELS

"Clifton Farm," for eggs, M. F. Von Dohren.....	8,324
"Clito," for cigars, Doctor Cigar Company.....	8,333
"Cream of Gainesville," for whisky, P. Schwarz & Co.....	8,330
"Crown of Kansas," for flour, Crocker & Robbins Co.....	8,325
"Fignut," for a confection, Lion Fig and Date Company.....	8,327
"Gus Thiele," for cigars, cigarettes, and smoking and chewing tobacco, G. Thiele.....	8,331
"Indian Herb Hair Tonic," for a hair tonic, K. Mason.....	8,319
"Kimmel's Combined Bill, Day Journal and Ledger Book," for account books, W. Kimmel.....	8,317
"Lovelace," for a shampoo and dandruff cure, Edmunds, Roehrborn & Co.....	8,321
"Morse's Stable Liniment," for a medicine, Morse & Stephenson.....	8,322
"Old English Hair Tonic," for a hair tonic, K. Mason.....	8,320
"Queen of Minnesota," for flour, Crocker & Robbins Co.....	8,326
"Roloto," for hats, R. L. Toplitz.....	8,318
"Snitz Edwards White Rat Whiskey," for whisky, S. Edwards.....	8,320
"The Chicago Rival," for cigars, Rifkin & Sherman.....	8,336
"The Hartford Times," for cigars, Wm. Boardman & Sons Co.....	8,335
"The Miner's Friend," for cigars, A. Pious.....	8,334
"Winner Brand Salmon," for salmon, George & Baker Co.....	8,323
"X. L. N. T.," for cigars, American Lithographic Company.....	8,332
"Zin-Din Lemonade," for a powder or preparation, G. H. Allen.....	8,328

PRINTS.

"A. M. S. & Co.," for sponges, A. Moses, Sons & Co.....	334
"Left-Hand Buffalo Pure Rye," for whisky, McCarty-Christy Company.....	331
"One of the 57," for a fluid for pickling, H. J. Heinz Company.....	332
"Sultar," for a cleansing compound, Sultar Company.....	333
"Tuskish Trophies," for cigarettes, S. Anar-gyros.....	326 to 330
"Vicerine, a Shoe of High Degree," for shoes, Shaw-Goding Shoe Company.....	335


A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of \$45 each. If complicated the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.

ENGINEER'S LICENSE. MECHANICS, ENGINEERS, FIREMEN, ELECTRICIANS, ETC.

40-page pamphlet containing questions asked by Examining Board of Engineers.

SENT FREE. GEORGE A. ZELLER, Publisher, Room 550, 118 S. Fourth Street, ST. LOUIS, MO.




The .. Improved **BELL ODOMETER**
APPLIED TO YOUR
AUTOMOBILE
.. OR ..
CARRIAGE

will give you the exact distance traveled, and announce each mile passed by the stroke of a bell.

Send for Descriptive Circular S.

S. H. DAVIS & CO.
Cor. Portland & Sudbury Sts., Boston, Mass.

LYON & HEALY'S BRASS BAND



Own Make
INSTRUMENTS. Indorsed by the great Jules Levy as the best in the world. Big Catalogue 400 illustrations. FREE. Positively the lowest prices on Band Instruments, Uniforms and Supplies of all kinds. Also contains Music and Instructions for New Bands. Lyon & Healy, Manufacturers, 38 Adams St., Chicago. (Lyon & Healy are the largest music house in the world—Editor.)


50 YEARS' EXPERIENCE
PATENTS
TRADE MARKS
DESIGNS
COPYRIGHTS & C.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbooks on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year: four months, \$1. Sold by all newsdealers.

MUNN & Co., 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.



BICYCLES BELOW COST

5000 high grade guaranteed 1901 MODELS, the overstock of one of the best known factories of the country, secured by us at one-half cost. **Four Models.....** High Grade **\$10 \$16** to **\$7 \$12**

Catalogues with large photographic engravings and full detailed specifications sent free to any address.

WE SHIP any bicycle ON APPROVAL to anyone without a cent deposit in advance and allow it to be ridden on

10 DAYS FREE TRIAL. You take absolutely no risk in ordering from us, as you do not need to pay a cent if the bicycle does not suit you.

500 Second Hand Wheels taken in trade by our Chicago retail stores, standard makes, many good as new, in each town. In exchange for a wheel to ride and

RIDER AGENTS WANTED to distribute a sample 1901 model bicycle. In your spare time you can make \$10 to \$50 a week besides having a wheel to ride for yourself.

WE WANT a reliable person in each town to distribute catalogues for us in exchange for a bicycle. Write today for free catalogue and our special offer.

MEAD CYCLE CO., Dept. 62 P. Chicago.

10c.-BLACK & WHITE PHOTOS-50.



To introduce our "Black and White" developer. For 10 Cents we will mail to any address enough developer to develop 50 4x5 prints such as Dixie, Velox or any developing paper. Everybody interested in photography should send for our new catalog. Prices the lowest. Developing, &c. 8x10 bromide enlargements, 35 cents.

Diamond Camera & Photo Supply Co., 240 B'way, N. Y.

KEEP POSTED ON AUTOMOBILES
THE HUB will post you. THE HUB is the leading carriage and automobile, the journal, and gives authentic information on automobiles.
Do not buy an automobile until you have read and studied THE HUB. At News-stands or by mail, 25 cents. Six months' subscription, \$1.00. **TRADE NEWS PUBLISHING CO., Room 8, 24 Murray Street, NEW YORK.**

AGENTS TO RIDE ECLIPSE CYCLES
We want a gentle man and a lady rider on an Eclipse Cycle in every town in the U. S. to introduce them. BIG MONEY for you if you can do it. Write for proposition.
SEYMOUR MFG. CO., 99 Chambers St., N. Y. Dept. 5.

THE HARRISON CONVEYOR—Electric Light and Power Station Equipment, Industrial Railways, Screens, Roller Screens, Elevators, Hoisting Engines, Clam Shell Buckets, Breaker Rolls, Picking Tables, Howe Standard Scales, Howe Gas and Gasoline Engines. For catalogue and prices, address the manufacturers.
BORDEN & SELLECK CO., 48-50 LAKE STREET, CHICAGO, ILL.

D. L. HOLDEN
14 SOUTH BROAD ST. PHILADELPHIA, PA.
SOLE MANUFACTURER
REGEALD ICE MACHINES
SEE FIRST PAGE, SCIENTIFIC AMERICAN, SEPT. 2, 1899.

THE ELECTRIC HEATER.—A VALUABLE paper, with working drawings of various forms of the electrical heaters, including electric soldering iron, electric pad for the sick, etc. 6 illustrations. SCIENTIFIC AMERICAN SUPPLEMENT 1112. Price 10 cents. For sale by Munn & Co. and all newsdealers.

SPECIAL PRICES 30% Trial. Guaranteed. Double and Combination Beam.
OSGOOD SCALE CO., 335 Central St., BINGHAMTON, N. Y.
Catalog Free. Write now.

17 JEWELLED
adjusted, patent regulator, stem wind and stem set, genuine
NATIONAL SPECIAL
movement. Ladies' or Gents' size. **WARRANTED 20 YEARS, 14K.** Gold plate hunting case, elegantly engraved. Fit like a king. No better watch made. Must be seen to be appreciated. Special offer for next 60 days, send your full name and address and we will send this watch C.O.D. with privilege to examine. If found satisfactory pay agent \$5.85 & express charges. A guarantee and beautiful chain & charm sent free with every watch. Write at once as this may not appear again. **NAT'L MFG. & IMPORTING CO., 554 Dearborn St., B 420, Chicago, Ill.**

What Do You Want To Buy?

We can tell you where to buy anything you want. Write us for the addresses of manufacturers in ANY line of business. Novelties, Special Tools, Machinery, Equipments, New Patent LABOR SAVING DEVICES. **MUNN & CO., Publishers of the SCIENTIFIC AMERICAN, 361 BROADWAY, NEW YORK.**

FOR MEN OF BRAINS Cortez CIGARS -MADE AT KEY WEST-

These Cigars are manufactured under the most favorable climatic conditions and from the mildest blends of Havana tobacco. If we had to pay the imported cigar tax our brands would cost double the money. Send for booklet and particulars.

CORTEZ CIGAR CO., KEY WEST.


THOROUGH INSPECTIONS
AND
INSURANCE
AGAINST LOSS
OR
DAMAGE
PROPERTY
AND
LOSS OF LIFE
AND
INJURY
TO PERSONS
CAUSED BY
STEAM-BOILER EXPLOSIONS

HARTFORD STEAM BOILER INSPECTION AND INSURANCE CO.
HARTFORD, CONN.

J. M. ALLEN, PRESIDENT
J. B. PIERCE, SECRETARY
L. B. BRAINERD, TREAS.

W. B. FRANKLIN, VICE PRESIDENT
F. B. ALLEN, 2ND VICE PRESIDENT
L. F. MIDDLEBROOK, ASST. SECY.

It Wins Its Way



into popular favor among the upper classes here and abroad. The


WINTON MOTOR CARRIAGE

is now universally recognized as the standard of excellence. Beautiful, durable, swift and sure. Easily controlled and regulated. Hydro-carbon (gasoline) system.

PRICE \$1,200.

THE WINTON MOTOR CARRIAGE CO.,
486 Belden Street, Cleveland, Ohio, U. S. A.
EASTERN DEPOT, 150-152 East 58th Street, New York.

KNOX Gasoline Runabout. WHY SO POPULAR?



Novel and improved engine. Entire absence of water. Strong and durable construction. Large carrying space in the body. Ample power and all changes of speed. 180 miles on the six gallons of fuel carried. No experiment. Used in all parts of the country. Very reliable on account of its extreme simplicity.

Weight 675 Pounds. Price \$750. Immediate Delivery.

Two new 1900 Model Wagons for sale at \$500 each.

KNOX AUTOMOBILE CO., - SPRINGFIELD, MASS.

Awarded 100% and the Official Blue Ribbon for a Perfect Run of 100 Miles Without a Stop.



This prize was given to the driver of one of our four-passenger pleasure automobiles, by the "Long Island Automobile Club" April 26th. Average time 15 miles per hour in a heavy rain and wind storm.

THE HAYNES-APPERTON CO., KOKOMO, IND., U. S. A.

Patee Motor Cycles, \$200.



No other make of Motor Cycle can maintain a speed anywhere near equal to this wonderful machine. It is light, strong, serviceable and reliable. Will go every time, any time and all the time. No experiment, no playing, fully guaranteed. Money refunded if not as described. Big trade discount. WRITE US.

PATEE BICYCLE CO., - Indianapolis, Ind., U. S. A.



GARDNER'S STOCK
CH. BISHOP & CO. 1012 N. CANAL ST. CHICAGO ILL. U.S.A.

Scales
All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Saws, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

Patents Protected

Against Infringers.
Dealers and Manufacturers of

PATENTED ARTICLES
PROTECTED

against dangerous litigation at a nominal cost.

ALSO COPYRIGHTS AND TRADEMARKS.

Booklet on application.

PATENT TITLE & GUARANTEE CO.,

CAPITAL \$500,000.00.

Tel. 5533 Cortlandt. 150 Broadway, New York.

WALTHAM WATCHES

Before 1854 there were no Waltham Watches nor any American Watches. To-day the tradition that one must go abroad for a good watch has been exploded by the American Waltham Watch Company.

"The Perfected American Watch", an illustrated book of interesting information about watches, will be sent free upon request.

American Waltham Watch Company,
Waltham, Mass.

WATCHES!


No advertisement can properly portray the striking effects produced in our watches. They are illustrated in our BLUE BOOK showing Ladies' Watches in all metals and exquisite enamels; our RED BOOK showing Men's and Boys' Watches with up-to-date attractive designs.

Either Blue or Red Book sent on application.
THE NEW ENGLAND WATCH CO.,
37 & 39 Maiden Lane, 149 State Street,
New York City, Chicago.
Spreckels Building, San Francisco.

CRACKS IN FLOORS

are unsightly, unclean and unsanitary. GRIPPIN'S WOOD, CRACK AND CREVICE FILLER is the only perfect remedy. A Paste, easily applied, elastic, adhesive, and non-shrinkable. Dirt and moth proof. Cost about 1/2c. per sq. ft. 5 lbs. will treat an average room. Price 20 cts. per lb. State the kind and condition of wood when ordering, and full instructions will be given. Is also the best filler for open-grained woods.

GRIPPIN MFG. CO., Lock Box L, Newark, New York.
(Inclose stamp for booklet.)



ELECTRIC VICTORIA.

Columbia AUTOMOBILES

In Sixth Year of Successful Service.

FORTY MILES ON ONE CHARGE OF BATTERIES.

IMPROVED 1901 MODELS

At Moderate Prices, For Ready Delivery.

Reliability, Simplicity, Cleanliness.


Send for 1901 Illustrated Catalogue and Revised Price List.

ELECTRIC VEHICLE CO., 100 BROADWAY, NEW YORK.

CHARTER ENGINE

USED ANY PLACE BY ANY ONE FOR ANY PURPOSE
FUEL—Gasoline, Gas, Distillate
Stationaries, Portables, Engines and Pumps, Hoisters

Send for Catalogue and Testimonials.
State Your Power Needs
CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.



HOW TO MAKE AN ELECTRICAL Furnace for Amateur's Use.—The utilization of 100 volt electric circuits for small furnace work. By N. Monroe Hopkins. This valuable article is accompanied by detailed working drawings on a large scale, and the furnace can be made by any amateur who is versed in the use of tools. This article is contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1152. Price 10 cents. For sale by MUNN & Co., 361 Broadway, New York City, or by any bookseller or newsdealer.


GAS ENGINE DETAILS.—A VALUABLE and fully illustrated article on this subject is contained in SUPPLEMENT No. 1292. Price 10 cents. For sale by Munn & Co. and all newsdealers.

A Reliable and Simple
FOUR CYLINDER Gasoline Motor
6 1/2 Brake Horse Power Guaranteed for Marine and Automobile use. Free from vibration, variable speed, starts on quarter turn. Prompt delivery. Additional information cheerfully given.
Catalogue for the asking.
MOTOR VEHICLE POWER CO., 1229 Spring Garden St. Philadelphia.
N.Y. Office, 62 Gold St.

MORROW COASTER BRAKE.
FITS ANY CYCLE 100,000 IN USE
ADDS PLEASURE AND SAFETY—ALL DEALERS SELL THEM.
RIDE 50 MILES—PEDAL ONLY 35. ECLIPSE MANUFACTURING CO., BOX X, ELMIRA, N.Y.
SEND FOR BOOKLET.

SAVAGE MAGAZINE RIFLE

.303 and 30-30 Caliber.



The Rifle of the 20th Century

BAKER & HAMILTON, San Francisco and Sacramento, Cal.
Pacific Coast Agents.
SAVAGE ARMS CO., UTICA, N. Y., U. S. A.
Catalogue A.

Williams' Shaving Stick

Lather
THICK
SOFT
CREAMY



SOOTHING
COOLING
AND
REFRESHING

"The Only Kind that Won't Dry on the Face"

SOLD EVERYWHERE.
Williams' Shaving Stick, 25c.
Genuine Yankee Shaving Soap, 10c.
Luxury Shaving Tablet, 25c.
Swiss Violet Shaving Cream, 50c.
Williams' Shaving Soap (Barbers'), 6 Round Cakes, 1 lb., 40c. Exquisite also for toilet.
Trial cake for 2c. stamp.
The only firm in the world making a specialty of SHAVING Soaps
THE J. B. WILLIAMS CO., Glastonbury, Ct.
LONDON PARIS DRESDEN SYDNEY

Chemistry of Manufacturing.

Testing, Perfecting, Introducing and Disposing of Chemical Patents, Processes, Formulas, etc. Utilization of Wastes and Unapplied Substances. Improvement and Invention of Processes and Products. Reduction of Manufacturing Costs. Experimental Investigation of Technical Problems. Working out Formulas for Manufacturing Technical Articles. Research Work for Manufacturers.

PETER T. AUSTEN, - 52 Beaver Street, New York.

STEWART'S WONDER

is the highest class Acetylene Gas Burner. All Lava Tips. A new argand burner \$2.50 highest candle power obtainable. Correspondence solicited.

STATE LINE MFG. CO., Chattanooga, Tenn., U. S. A.

GRAND PRIZE, PARIS, 1900.
HIGHEST AWARD POSSIBLE.

FROM A TO Z

THE SMITH PREMIER WILL FULLY MEET YOUR EVERY TYPEWRITER REQUIREMENT. BUILT RIGHT—WORKS RIGHT. USED BY THE LEADING MANUFACTURERS AND MERCHANTS EVERYWHERE. BECAUSE THE MOST ECONOMICAL TO OWN. PRINTED MATTER FREE.

THE SMITH PREMIER TYPEWRITER CO.
SYRACUSE, N.Y. U.S.A.

The Typewriter Exchange

1 1/2 Barclay St., NEW YORK
124 La Salle St., CHICAGO
38 Bromfield St., BOSTON
817 Wyandotte St., KANSAS CITY, MO.
209 North 9th St., ST. LOUIS, MO.
432 Diamond St., PITTSBURGH, PA.
3 West Baltimore St., BALTIMORE, MD.
536 California St., SAN FRANCISCO, CAL.
We will save you from 10 to 50% on Typewriters of all makes. Send for Catalogue.

ARMATURE WINDING, RIGHT AND Left Handed.—An important paper for all amateurs. 17 illustrations. SCIENTIFIC AMERICAN SUPPLEMENT, No. 1139, price 10 cents. For sale by Munn & Co. and all newsdealers. Send for catalogue.

The No. 4 YOST WRITING MACHINE



The distinctive features of the Yost Machine, permanent alignment, direct inking, beautiful work, strength, simplicity, and durability are shown in perfection in the No. 4 Model.

Yost Writing Machine Co.

NEW YORK CITY. LONDON, ENG.

JESSOP'S STEEL THE VERY BEST FOR TOOLS, SAWS, ETC.
WM. JESSOP & SONS L.B. 91 JOHN ST. NEW YORK